BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Restoration and Improvements of roads and drains in A Y R Layout, Shettihalli village, RR Layout of Chikkasandra village and Abbigere village roads,BTS Village,Vishveshwaraiah village,Royal Enclave and Sidedahalli Old village roads dugged by BWSSB to lay water supply and UGD lines under 110 villages in ward no.12 &14 Shettihalli.

JOB NUMBER.:								Est. Amount =	1800.00	Lakhs
Sl. No	Description of Work	Road ID	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
1	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)									
	KPWD S.R 2018-19		lt. No.	5.33.		Pg.No.	27			
	a) 7.5cm thick									
	Medarahalli Village									
	railway station track to Dead End									
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		2	620.00	1.35		1674.00		
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-140 Sun Sine School Front Road			2	140.00	1.35		378.00		
	Ch:00-105 G. Mukesh House Road	w0271		2	105.00	1.35		283.50		
	Ch:105-130 G. Mukesh House Road	w0271		2	25.00	1.35		67.50		
	Ch:00-25 Sri Sai Nivasa Front Road	w0260		1	25.00	1.35		33.75		
	RHS Road Raj Kaluve to Sri Swamy Bakery									
	Ch:00-74 Athira House LHS Road			2	74.00	1.35		199.80		
	Ch:00-75 Athira House RHS Road			2	75.00	1.35		202.50		
	Ch:00-115 Sri Chandrappa nilaya beside road			2	115.00	1.35		310.50		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-85 Siddeswara store Beside Road	w0206		2	85.00	1.35		229.50		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		2	35.00	1.35		94.50		
	Ch:00-100 JMJ Provision Store	w0215		2	100.00	1.35		270.00		
	Ch:00-62 Ameen Maneil House Front Road	w0217		2	62.00	1.35		167.40		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		2	58.00	1.35		156.60		
	Ch:00-40 Coss Road			2	40.00	1.35		108.00		
	Ch:00-55 Sachith House Beside Road	w0210		2	55.00	1.35		148.50		
	Ch:00-144 Sachith House Front Road	w0204		2	144.00	1.35		388.80		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		2	40.00	1.35		108.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		2	88.00	1.35		237.60		
	Ch:00-60 Virabramendra House Front Road	w0200		2	60.00	1.35		162.00		
	Ch:60-110	w0200		2	50.00	1.35		135.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		2	185.00	1.35		499.50		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		2	120.00	1.35		324.00		
	Ch:00-40 Cross Road 1	w0225		2	40.00	1.35		108.00		
	Ch:00-56 Cross Road 2	w0231		2	56.00	1.35		151.20		
	LHS Road Abbigere Road to RR Institution Compound									
	Ch:00-92 Sapthagiri House Beside			2	92.00	1.35		248.40		
	Ch:00-95 LakshmiNilaya Beside Road			2	95.00	1.35		256.50		
	Shetihalli Village									
	Brindavana Layout									
	Ch: 00 -65 6th c/s road	w0946		2	65.00	1.35		175.50		
	Ch: 00 -100 5th c/s road	w0950		2	100.00	1.35		270.00		
	Ch: 00 -130 4th c/s road (Behtar store)	w0954		2	130.00	1.35		351.00		
	Ch: 00 -55 1st c/s road (Eskay hospital)	w1085		2	55.00	1.35		148.50		
	Ch: 00 -100 2nd c/s road	w0958		2	100.00	1.35		270.00		
	Kaveri Layout					1.35				
	Ch: 00 -150 4th c/s road	w0944		2	150.00	1.35		405.00		
	Ch: 00 -180 5th c/s road	w0952		2	180.00	1.35		486.00		
	Ch: 00 -120 6th c/s road	w0956		2	120.00	1.35		324.00		
	Ramakrishna Layout									
	Alladamara To Malasandara Road RHS Road									

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:00-125 Sri Ganesha Trades Beside	w0967		2	125.00	1.35		337.50		
	Ch:00-121 Pavana Nilaya Road	w0961		2	121.00	1.35		326.70		
	Ch:00-68 Pavana Nilaya Front Road	w0800		2	68.00	1.35		183.60		
	Byraveshwara nagara									
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		2	120.00	1.35		324.00		
	Ch:00-137 Park Beside Road	w0951		2	137.00	1.35		369.90		
	Ch:00-192 2nd Cross Road	w0943		2	192.00	1.35		518.40		
	Ch:00-195 3rd Cross Road	w0941		2	195.00	1.35		526.50		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		2	110.00	1.35		297.00		
	Ch:00-120 Cross Road	w0935		2	120.00	1.35		324.00		
	Ch:00-130 Cross Road	w0937		2	130.00	1.35		351.00		
	A Y R Layout					1.35				
	Ch:00-85 Saptagiri Nilaya	w0953		2	85.00	1.35		229.50		
	Ch:00-70 Padma Washing beside	w0813		2	70.00	1.35		189.00		
	Ch:00-83 Mukambika Stores Beside Road	w0827		2	83.00	1.35		224.10		
	Ch:00-80 Mukambika Stores Front Road	w0945		2	80.00	1.35		216.00		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		2	85.00	1.35		229.50		
	Ch:00-90 Gurusai Front Road	w0823		2	90.00	1.35		243.00		
	Ch:00-95 Cross Road			2	95.00	1.35		256.50		
	AGB Layout									
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		2	542.00	1.35		1463.40		
	Ch:00-100 3rd main Road	w0743		2	100.00	1.35		270.00		
	Ch:00-160 Manasa school Road	w0630		2	160.00	1.35		432.00		
	Ch:00-147 6th C Main Road	w0632		2	140.00	1.35		378.00		
	Ch:00-130 11th c/s Road	w0741		2	130.00	1.35		351.00		
	Ch:00-170 12th Main Road	w0739		2	160.00	1.35		432.00		
	Ch:00-400 11th main road	w0660		2	350.00	1.35		945.00		
	Ch:00-148 13th c/s Road			2	148.00	1.35		399.60		
	Ch:00-100 Divya apparel	w0682		2	100.00	1.35		270.00		
	Sidedahalli Village Village									
	Sampangiramaiah Layout									
	Ch:00-70 1st c\s road	w0219		2	70.00	1.35		189.00		
	Ch:00-205 c\s road 2	w0230		2	205.00	1.35		553.50		
	Ch:00-167 2nd c\s road	w0215		2	167.00	1.35		450.90		
	Ch:00-140 c\s road 3	w0209		2	140.00	1.35		378.00		
	Ch:00- 126 c\s road 4	w0115		2	126.00	1.35		340.20		
	Kirloskar Layout									
	Ch:00-169 New trends	w0109		2	169.00	1.35		456.30		
	Ch:00-125 3rd c\s road	w0202		2	125.00	1.35		337.50		
	Ch:00-129 4th c\s road	w0204		2	129.00	1.35		348.30		
	Ch:00-105 8th c\s road	w0103		2	105.00	1.35		283.50		
	Ch:00-65 6th c\s road	w0212		2	65.00	1.35		175.50		
	Ch:00-68 7th c\s road	w0105		2	68.00	1.35		183.60		
	Ch:00-105 5th c\s road	w0107		2	105.00	1.35		283.50		
	Ch:00-110 13th c\s road	w0214		2	110.00	1.35		297.00		
	Ch:00-72 14th c\s road	w0095		2	72.00	1.35		194.40		
	Ch:00-51 12th c\s road	w0210		2	51.00	1.35		137.70		
	Ch:00-121 11th c\s road	w0206		2	121.00	1.35		326.70		
	Ch:00-71 15th c\s road	w0093		2	71.00	1.35		191.70		
	Ch:00-121 10t c\s road	w0200		2	121.00	1.35		326.70		
	Ch:00-140 26th c\s road	w0174		2	140.00	1.35		378.00		
	Ch:00-113 27th c\s road	w0066		2	113.00	1.35		305.10		
	Ch:00-134 20thc\s road			2	134.00	1.35		361.80		
	Ch:00-129 25thc\s road	w0176		2	129.00	1.35		348.30		
	Ch:00-50 24th c\s road	w0180		2	50.00	1.35		135.00		
	Ch:00-254 22nd c\s road	w0190		2	254.00	1.35		685.80		
	Ch:00-150 28th c\s road	w0194		2	150.00	1.35		405.00		
	Abbigere Village									
	vijaya lakshmi layout									
	1st Cross Road Ch:00-55	w0051		2	55.00	1.35		148.50		
	Cross Road Ch:00-55	w0055		2	55.00	1.35		148.50		
	Cross Road Ch:00-40	w1023		2	40.00	1.35		108.00		
	Cross Road Ch:00-60	w0051		2	60.00	1.35		162.00		
	3rd Cross Road Ch:00-85	w0077		2	85.00	1.35		229.50		
	4th Cross Road Ch:00-25	w0057		2	25.00	1.35		67.50		
	Ch:00-250 1st Main Road	w0106		2	250.00	1.35		675.00		
	Ch:00-250 MAA BEE Stores	w0114		2	250.00	1.35		675.00		
	1st Main Road Ch:00-183	w0073		2	183.00	1.35		494.10		
	1st Cross Road Ch:00-190	w0075		2	190.00	1.35		513.00		

Sl. No	Description of Work	Road ID	Unit	No		Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
	R O Plant Opp Road										
	Ch:00-149 R O Plant frant road	w0047		2		149.00	1.35		402.30		
	Ch:00-116 1st Cross Road	w0092		2		116.00	1.35		313.20		
	Ch:00-110 2nd Cross Road	w0098		2		110.00	1.35		297.00		
	Chikkasandra Village										
	Sapthgiri College Main Road RHS										
	Ch:0-100 4th Cross Road	w0839		2		100.00	1.35		270.00		
	Ch:0-122 3rd Cross Road	w0847		2		122.00	1.35		329.40		
	Ch:0-30 5th Cross Connecting road	w1004		2		30.00	1.35		81.00		
	Ch:0-125 2nd Cross Road	w0843		2		125.00	1.35		337.50		
	Ch:0-120 5th Cross Road	w0853		2		120.00	1.35		324.00		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		2		200.00	1.35		540.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		2		40.00	1.35		108.00		
	Ch:0-110 7th Cross Road (chicken World Front)	w0857		2		110.00	1.35		297.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1		160.00	1.35		216.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		2		220.00	1.35		594.00		
	Ch:0-156 7th Cross Road	w0690		2		156.00	1.35		421.20		
	Ch:0-145 Gokul Motors Beside Road	w0863		2		145.00	1.35		391.50		
	Ch:0-110 6th Cross Road	w0696		2		100.00	1.35		270.00		
	Ch:0-120 5th Cross Road	w0702		2		120.00	1.35		324.00		
	Ch:0-116 4th Cross Road	w0704		2		116.00	1.35		313.20		
	b) 10cm thick										
	railway station track to Dead End										
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		2		510.00	0.90		918.00		
	LHS Road Sri Swamy Bakery to Raj Kaluve										
	Ch:00-146 Sri Lakshmi Beside	w0271		2		146.00	0.90		262.80		
	Ch:00-25 Sri Maruthi Nilaya	w0267		2		25.00	0.90		45.00		
	Ch:25-111 Sri Maruthi Nilaya	w0268		2		86.00	0.90		154.80		
	RHS Road Raj Kaluve to Sri Swamy Bakery										
	Ch:00-105 Raja Kaluve Beside Road	w0265		2		105.00	0.90		189.00		
	Ch:00-122 Raunak Tower Beside Road	w0269		2		122.00	0.90		219.60		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-55 Manjushree Bakery Beside	w0247		2		55.00	0.90		99.00		
	Ch:00-57 Rusoil Bakery Beside	w0251		2		57.00	0.90		102.60		
	Ch:00-81 3rd Cross Road	w0253		2		81.00	0.90		145.80		
	Ch:00-73 RR Institution Road	w0255		2		73.00	0.90		131.40		
	Ch:00-70 5th Cross Road	w0257		2		70.00	0.90		126.00		
	Shettihalli Village										
	Kaveri Layout										
	Ch: 00 -80 1st c/s road LHS	w0962		1		80.00	0.90		72.00		
	Ch: 00 -85 2nd c/s road LHS	w0960		1		85.00	0.90		76.50		
	Ch: 00 -120 3rd c/s road	w0956		2		120.00	0.90		216.00		
	AGB Layout										
	Ch:00-770 60 feet road	w0737		2		650.00	0.90		1170.00		
	Ch:00-260 Family Store Front Road	w0753		2		230.00	0.90		414.00		
	Deduct 20% for damaged/missing slab			-1		8185.23			-8185.23		
								Total Qty	**32740.92**	**111.30**	**36,44,064.40**
2	Earthwork excavation by manual means for roads, drains & similar works in in hard soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.										
	KPWD S.R 2018-19		It. No.		19.10		Pg.No.	143			
	Desilting Drain										
	Medarahalli Village										
	railway station track to Dead End										
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		2		620.00	0.45	0.25	139.50		
	LHS Road Sri Swamy Bakery to Raj Kaluve										
	Ch:00-140 Sun Sine School Front Road			2		140.00	0.45	0.25	31.50		
	Ch:00-105 G. Mukesh House Road	w0271		2		105.00	0.45	0.25	23.63		
	Ch:105-130 G. Mukesh House Road	w0271		2		25.00	0.45	0.25	5.63		

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:00-25 Sri Sai Nivasa Front Road	w0260		1	25.00	0.45	0.25	2.81		
	RHS Road Raj Kaluve to Sri Swamy Bakery									
	Ch:00-74 Athira House LHS Road			2	74.00	0.45	0.25	16.65		
	Ch:00-75 Athira House RHS Road			2	75.00	0.45	0.25	16.88		
	Ch:00-115 Sri Chandrappa nilaya beside road			2	115.00	0.45	0.25	25.88		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-35 Mayura Bakery Front Road	w0229		2	35.00	0.45	0.25	7.88		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1	58.00	0.45	0.25	6.53		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-85 Siddeswara store Beside Road	w0206		2	85.00	0.45	0.25	19.13		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		2	35.00	0.45	0.25	7.88		
	Ch:00-100 JMJ Provision Store	w0215		2	100.00	0.45	0.25	22.50		
	Ch:00-62 Ameen Maneil House Front Road	w0217		2	62.00	0.45	0.25	13.95		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		2	58.00	0.45	0.25	13.05		
	Ch:00-40 Coss Road			2	40.00	0.45	0.25	9.00		
	Ch:00-55 Sachith House Beside Road	w0210		2	55.00	0.45	0.25	12.38		
	Ch:00-144 Sachith House Front Road	w0204		2	144.00	0.45	0.25	32.40		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		2	40.00	0.45	0.25	9.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		2	88.00	0.45	0.25	19.80		
	Ch:00-60 Virabramendra House Front Road	w0200		2	60.00	0.45	0.25	13.50		
	Ch:60-110	w0200		2	50.00	0.45	0.25	11.25		
	Ch:00-185 Nanjunda swami Front Road	w0215		2	185.00	0.45	0.25	41.63		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		2	120.00	0.45	0.25	27.00		
	Ch:00-40 Cross Road 1	w0225		2	40.00	0.45	0.25	9.00		
	Ch:00-56 Cross Road 2	w0231		2	56.00	0.45	0.25	12.60		
	LHS Road Abbigere Road to RR Institution Compound									
	Ch:00-92 Sapthagiri House Beside			2	92.00	0.45	0.25	20.70		
	Ch:00-95 LakshmiNilaya Beside Road			2	95.00	0.45	0.25	21.38		
	Shetihalli Village									
	Brindavana Layout									
	Ch: 00 -65 6th c/s road	w0946		2	65.00	0.45	0.25	14.63		
	Ch: 00 -100 5th c/s road	w0950		2	100.00	0.45	0.25	22.50		
	Ch: 00 -130 4th c/s road (Behtar store)	w0954		2	130.00	0.45	0.25	29.25		
	Ch: 00 -55 1st c/s road (Eskay hospital)	w1085		2	55.00	0.45	0.25	12.38		
	Ch: 00 -100 2nd c/s road	w0958		2	100.00	0.45	0.25	22.50		
	Kaveri Layout									
	Ch: 00 -150 4th c/s road	w0944		2	150.00	0.45	0.25	33.75		
	Ch: 00 -180 5th c/s road	w0952		2	180.00	0.45	0.25	40.50		
	Ch: 00 -120 6th c/s road	w0956		2	120.00	0.45	0.25	27.00		
	Ramakrishna Layout									
	Alladamara To Malasandara Road RHS Road									
	Ch:00-125 Sri Ganesha Trades Beside	w0967		2	125.00	0.45	0.25	28.13		
	Ch:00-121 Pavana Nilaya Road	w0961		2	121.00	0.45	0.25	27.23		
	Ch:00-68 Pavana Nilaya Front Road	w0800		2	68.00	0.45	0.25	15.30		
	Byraveshwara nagara									
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		2	120.00	0.45	0.25	27.00		
	Ch:00-137 Park Beside Road	w0951		2	137.00	0.45	0.25	30.83		
	Ch:00-192 2nd Cross Road	w0943		2	192.00	0.45	0.25	43.20		
	Ch:00-195 3rd Cross Road	w0941		2	195.00	0.45	0.25	43.88		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		2	110.00	0.45	0.25	24.75		
	Ch:00-120 Cross Road	w0935		2	120.00	0.45	0.25	27.00		
	Ch:00-130 Cross Road	w0937		2	130.00	0.45	0.25	29.25		
	A Y R Layout									
	Ch:00-85 Saptagiri Nilaya	w0953		2	85.00	0.45	0.25	19.13		
	Ch:00-70 Padma Washing beside	w0813		2	70.00	0.45	0.25	15.75		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-83 Mukambika Stores Beside Road	w0827		2		83.00	0.45	0.25	18.68		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		2		85.00	0.45	0.25	19.13		
	Ch:00-90 Gurusai Front Road	w0823		2		90.00	0.45	0.25	20.25		
	Ch:00-95 Cross Road			2		95.00	0.45	0.25	21.38		
	AGB Layout										
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		2		542.00	0.45	0.25	121.95		
	Ch:00-100 3rd main Road	w0743		2		100.00	0.45	0.25	22.50		
	Ch:00-160 Manasa school Road	w0630		2		160.00	0.45	0.25	36.00		
	Ch:00-147 6th C Main Road	w0632		2		140.00	0.45	0.25	31.50		
	Ch:00-130 11th c/s Road	w0741		2		130.00	0.45	0.25	29.25		
	Ch:00-170 12th Main Road	w0739		2		160.00	0.45	0.25	36.00		
	Ch:00-400 11th main road	w0660		2		350.00	0.45	0.25	78.75		
	Ch:00-148 13th c/s Road			2		148.00	0.45	0.25	33.30		
	Ch:00-100 Divya apparel	w0682		2		100.00	0.45	0.25	22.50		
	Sidedahalli Village Village										
	Sampangiramaiah Layout										
	Ch:00-70 1st c\s road	w0219		2		70.00	0.45	0.25	15.75		
	Ch:00-205 c\s road 2	w0230		2		205.00	0.45	0.25	46.13		
	Ch:00-167 2nd c\s road	w0215		2		167.00	0.45	0.25	37.58		
	Ch:00-140 c\s road 3	w0209		2		140.00	0.45	0.25	31.50		
	Ch:00- 126 c\s road 4	w0115		2		126.00	0.45	0.25	28.35		
	Kirloskar Layout										
	Ch:00-169 New trends	w0109		2		169.00	0.45	0.25	38.03		
	Ch:00-125 3rd c\s road	w0202		2		125.00	0.45	0.25	28.13		
	Ch:00-129 4th c\s road	w0204		2		129.00	0.45	0.25	29.03		
	Ch:00-105 8th c\s road	w0103		2		105.00	0.45	0.25	23.63		
	Ch:00-65 6th c\s road	w0212		2		65.00	0.45	0.25	14.63		
	Ch:00-68 7th c\s road	w0105		2		68.00	0.45	0.25	15.30		
	Ch:00-105 5th c\s road	w0107		2		105.00	0.45	0.25	23.63		
	Ch:00-110 13th c\s road	w0214		2		110.00	0.45	0.25	24.75		
	Ch:00-72 14th c\s road	w0095		2		72.00	0.45	0.25	16.20		
	Ch:00-51 12th c\s road	w0210		2		51.00	0.45	0.25	11.48		
	Ch:00-121 11th c\s road	w0206		2		121.00	0.45	0.25	27.23		
	Ch:00-71 15th c\s road	w0093		2		71.00	0.45	0.25	15.98		
	Ch:00-121 10t c\s road	w0200		2		121.00	0.45	0.25	27.23		
	Ch:00-140 26th c\s road	w0174		2		140.00	0.45	0.25	31.50		
	Ch:00-113 27th c\s road	w0066		2		113.00	0.45	0.25	25.43		
	Ch:00-134 20thc\s road			2		134.00	0.45	0.25	30.15		
	Ch:00-129 25thc\s road	w0176		2		129.00	0.45	0.25	29.03		
	Ch:00-50 24th c\s road	w0180		2		50.00	0.45	0.25	11.25		
	Ch:00-254 22nd c\s road	w0190		2		254.00	0.45	0.25	57.15		
	Ch:00-150 28th c\s road	w0194		2		150.00	0.45	0.25	33.75		
	Abbigere Village										
	vijaya lakshmi layout										
	1st Cross Road Ch:00-55	w0051		2		55.00	0.45	0.25	12.38		
	Cross Road Ch:00-55	w0055		2		55.00	0.45	0.25	12.38		
	Cross Road Ch:00-40	w1023		2		40.00	0.45	0.25	9.00		
	Cross Road Ch:00-60	w0051		2		60.00	0.45	0.25	13.50		
	3rd Cross Road Ch:00-85	w0077		2		85.00	0.45	0.25	19.13		
	4th Cross Road Ch:00-25	w0057		2		25.00	0.45	0.25	5.63		
	Ch:00-250 1st Main Road	w0106		2		250.00	0.45	0.25	56.25		
	Ch:00-250 MAA BEE Stores	w0114		2		250.00	0.45	0.25	56.25		
	1st Main Road Ch:00-183	w0073		2		183.00	0.45	0.25	41.18		
	1st Cross Road Ch:00-190	w0075		2		190.00	0.45	0.25	42.75		
	R O Plant Opp Road										
	Ch:00-149 R O Plant frant road	w0047		2		149.00	0.45	0.25	33.53		
	Ch:00-116 1st Cross Road	w0092		2		116.00	0.45	0.25	26.10		
	Ch:00-110 2nd Cross Road	w0098		2		110.00	0.45	0.25	24.75		
	Chikkasandra Village										
	Sapthgiri College Main Road RHS										
	Ch:0-100 4th Cross Road	w0839		2		100.00	0.45	0.25	22.50		
	Ch:0-122 3rd Cross Road	w0847		2		122.00	0.45	0.25	27.45		
	Ch:0-30 5th Cross Connecting road	w1004		2		30.00	0.45	0.25	6.75		
	Ch:0-125 2nd Cross Road	w0843		2		125.00	0.45	0.25	28.13		
	Ch:0-120 5th Cross Road	w0853		2		120.00	0.45	0.25	27.00		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		2		200.00	0.45	0.25	45.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		2		40.00	0.45	0.25	9.00		
	Ch:0-110 7th Cross Road (chicken World Front)	w0857		2		110.00	0.45	0.25	24.75		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1		160.00	0.45	0.25	18.00		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		2		220.00	0.45	0.25	49.50		
	Ch:0-156 7th Cross Road	w0690		2		156.00	0.45	0.25	35.10		
	Ch:0-145 Gokul Motors Beside Road	w0863		2		145.00	0.45	0.25	32.63		
	Ch:0-110 6th Cross Road	w0696		2		100.00	0.45	0.25	22.50		
	Ch:0-120 5th Cross Road	w0702		2		120.00	0.45	0.25	27.00		
	Ch:0-116 4th Cross Road	w0704		2		116.00	0.45	0.25	26.10		
	CC Drain desilt										
	railway station track to Dead End										
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		2		510.00	0.60	0.25	153.00		
	LHS Road Sri Swamy Bakery to Raj Kaluve										
	Ch:00-146 Sri Lakshmi Beside	w0271		2		146.00	0.60	0.25	43.80		
	Ch:00-25 Sri Maruthi Nilaya	w0267		2		25.00	0.60	0.25	7.50		
	Ch:25-111 Sri Maruthi Nilaya	w0268		2		86.00	0.60	0.25	25.80		
	RHS Road Raj Kaluve to Sri Swamy Bakery										
	Ch:00-105 Raja Kaluve Beside Road	w0265		2		105.00	0.60	0.25	31.50		
	Ch:00-122 Raunak Tower Beside Road	w0269		2		122.00	0.60	0.25	36.60		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-55 Manjushree Bakery Beside	w0247		2		55.00	0.60	0.25	16.50		
	Ch:00-57 Rusoil Bakery Beside	w0251		2		57.00	0.60	0.25	17.10		
	Ch:00-81 3rd Cross Road	w0253		2		81.00	0.60	0.25	24.30		
	Ch:00-73 RR Institution Road	w0255		2		73.00	0.60	0.25	21.90		
	Ch:00-70 5th Cross Road	w0257		2		70.00	0.60	0.25	21.00		
	Shettihalli Village										
	Kaveri Layout										
	Ch: 00 -80 1st c/s road LHS	w0962		1		80.00	0.60	0.25	12.00		
	Ch: 00 -85 2nd c/s road LHS	w0960		1		85.00	0.60	0.25	12.75		
	Ch: 00 -120 3rd c/s road	w0956		2		120.00	0.60	0.25	36.00		
	AGB Layout										
	Ch:00-770 60 feet road	w0737		2		650.00	0.60	0.25	195.00		
	Ch:00-260 Family Store Front Road	w0753		2		230.00	0.60	0.25	69.00		
	New Culvert										
	Cross Roads			45		6.50	1.20	1.20	421.20		
	Earthwork for Road										
	New BC Road										
	LHS Road Sri Swamy Bakery to Raj Kaluve										
	Ch:00-140 Sun Sine School Front Road			1		140.00	6.00	0.30	252.00		
	Ch:00-130 G. Mukesh House Road			1		130.00	4.20	0.30	163.80		
	Ch:00-146 Sri Lakshmi Beside	w0271		1		146.00	4.50	0.30	197.10		
	Ch:00-38 Padma House Front Road			1		38.00	4.80	0.30	54.72		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1		25.00	4.00	0.30	30.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1		25.00	4.00	0.30	30.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1		86.00	5.00	0.30	129.00		
	RHS Road Raj Kaluve to Sri Swamy Bakery										
	Ch:00-105 Raja Kaluve Beside Road	w0265		1		105.00	4.70	0.30	148.05		
	Ch:00-122 Raunak Tower Beside Road	w0269		1		122.00	4.50	0.30	164.70		
	Ch:00-74 Athira House LHS Road			1		74.00	5.00	0.30	111.00		
	Ch:00-75 Athira House RHS Road			1		75.00	5.00	0.30	112.50		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1		115.00	5.00	0.30	172.50		
	railway station track to Dead End										
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		1		620.00	5.60	0.30	1041.60		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-35 Mayura Bakery Front Road	w0258	Cum	1		35.00	4.00	0.30	42.00		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1		58.00	3.50	0.30	60.90		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-55 Manjushree Bakery Beside	w0267		1		55.00	5.00	0.30	82.50		
	Ch:00-57 Rusoil Bakery Beside	w0255		1		57.00	5.00	0.30	85.50		
	Ch:00-81 3rd Cross Road	w0253		1		81.00	5.00	0.30	121.50		
	Ch:00-73 RR Institution Road	w0251		1		73.00	5.00	0.30	109.50		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-70 Silver Spring International School Road	w0247		1		70.00	5.00	0.30	105.00		
	Ch:00-85 Siddeswara store Beside Road	w0206		1		85.00	4.00	0.30	102.00		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1		35.00	4.00	0.30	42.00		
	Ch:00-100 JMJ Provision Store	w0215		1		100.00	4.50	0.30	135.00		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1		62.00	4.00	0.30	74.40		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1		58.00	4.00	0.30	69.60		
	Ch:00-40 Coss Road			1		40.00	4.00	0.30	48.00		
	Ch:00-55 Sachith House Beside Road	w0210		1		55.00	4.00	0.30	66.00		
	Ch:00-144 Sachith House Front Road	w0204		1		144.00	4.00	0.30	172.80		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1		40.00	4.00	0.30	48.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		1		88.00	4.00	0.30	105.60		
	Ch:00-60 Virabramendra House Front Road	w0200		1		60.00	4.50	0.30	81.00		
	Ch:60-110	w0200		1		50.00	4.80	0.30	72.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		1		185.00	4.00	0.30	222.00		
	Ch:00-155 Kushi backery opp road	w0229		1		155.00	4.00	0.30	186.00		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1		120.00	4.00	0.30	144.00		
	Ch:00-40 Cross Road 1	w0225		1		40.00	4.00	0.30	48.00		
	Ch:00-56 Cross Road 2	w0231		1		56.00	4.00	0.30	67.20		
	Shettihalli Village										
	Ramakrishna Layout										
	Alladamara To Malasandara Road RHS Road										
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1		125.00	4.50	0.30	168.75		
	Ch:00-121 Pavana Nilaya Road	w0961		1		121.00	4.50	0.30	163.35		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1		68.00	4.50	0.30	91.80		
	Byraveshwara nagara										
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1		120.00	4.50	0.30	162.00		
	Ch:00-137 Park Beside Road	w0951		1		137.00	4.50	0.30	184.95		
	Ch:00-192 2nd Cross Road	w0943		1		192.00	4.50	0.30	259.20		
	Ch:00-195 3rd Cross Road	w0941		1		195.00	4.50	0.30	263.25		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1		110.00	4.50	0.30	148.50		
	Ch:00-120 Cross Road	w0935		1		120.00	4.00	0.30	144.00		
	Ch:00-130 Cross Road	w0937		1		130.00	4.00	0.30	156.00		
	A Y R Layout										
	Ch:00-110 Hotel Taste Beside Road			1		110.00	4.50	0.30	148.50		
	Ch:00-85 Saptagiri Nilaya	w0953		1		85.00	4.50	0.30	114.75		
	Ch:00-70 Padma Washing beside	w0813		1		70.00	4.50	0.30	94.50		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1		83.00	4.50	0.30	112.05		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1		85.00	4.50	0.30	114.75		
	Ch:00-90 Gurusai Front Road	w0823		1		90.00	4.50	0.30	121.50		
	Ch:00-95 Cross Road			1		95.00	4.50	0.30	128.25		
	AGB Layout										
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1		565.00	6.00	0.30	1017.00		
	Ch:00-100 3rd main Road	w0743		1		100.00	5.50	0.30	165.00		
	Ch:00-148 6th c/s Road	w0620		1		148.00	6.00	0.30	266.40		
	Ch:00-147 6th C Main Road	w0632		1		147.00	5.50	0.30	242.55		
	Ch:00-130 11th Cross Road	w0741		1		130.00	5.50	0.30	214.50		
	Ch:00-127 13th c/s road	w0771		1		127.00	6.30	0.30	240.03		
	Ch:127-237 13th c/s Road	w0771		1		110.00	5.50	0.30	181.50		
	Ch:00-100 Divya apparel	w0682		1		100.00	5.20	0.30	156.00		
	Ch:00-160 Manasa school Road	w0630		1		160.00	5.50	0.30	264.00		
	Sidedahalli Village Village										
	Sampangiramaiah Layout										
	Ch:00-70 1st c\s road	w0418		1		70.00	4.80	0.30	100.80		
	Ch:00-205 c\s road 2	w0230		1		205.00	5.80	0.30	356.70		
	Ch:00-167 2nd c\s road	w0215		1		167.00	5.20	0.30	260.52		
	Ch:00-140 c\s road 3	w0209		1		140.00	4.80	0.30	201.60		
	Ch:00- 126 c\s road 4	w0115		1		126.00	4.80	0.30	181.44		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Kirloskar Layout										
	Ch:00-169 New trends	w0109		1		169.00	5.00	0.30	253.50		
	Ch:00-176 9th c\s road	w0101		1		176.00	5.20	0.30	274.56		
	Ch:00-125 3rd c\s road	w0202		1		125.00	6.00	0.30	225.00		
	Ch:00-129 4th c\s road	w0204		1		129.00	5.50	0.30	212.85		
	Ch:00-105 8th c\s road	w0103		1		105.00	5.00	0.30	157.50		
	Ch:00-65 6th c\s road	w0212		1		65.00	5.50	0.30	107.25		
	Ch:00-68 7th c\s road	w0105		1		68.00	5.00	0.30	102.00		
	Ch:00-105 5th c\s road	w0103		1		105.00	5.00	0.30	157.50		
	Ch:00-110 13th c\s road	w0214		1		110.00	5.00	0.30	165.00		
	Ch:00-72 14th c\s road	w0095		1		72.00	5.50	0.30	118.80		
	Ch:00-51 12th c\s road	w0210		1		51.00	4.50	0.30	68.85		
	Ch:00-121 11th c\s road	w0206		1		121.00	4.50	0.30	163.35		
	Ch:00-71 15th c\s road	w0093		1		71.00	4.20	0.30	89.46		
	Ch:00-121 10t c\s road	w0200		1		121.00	5.20	0.30	188.76		
	Ch:00-140 26th c\s road	w0174		1		140.00	5.00	0.30	210.00		
	Ch:00-113 27th c\s road	w0066		1		113.00	5.00	0.30	169.50		
	Ch:00-134 20thc\s road			1		134.00	5.20	0.30	209.04		
	Ch:00-129 25thc\s road	w0176		1		129.00	5.20	0.30	201.24		
	Ch:00-50 24th c\s road	w0180		1		50.00	5.00	0.30	75.00		
	Ch:00-254 22nd c\s road	w0190		1		254.00	5.20	0.30	396.24		
	Ch:00-92 21st c\s road			1		92.00	5.00	0.30	138.00		
	Ch:00-150 28th c\s road	w0194		1		150.00	5.20	0.30	234.00		
	Abbigere Village										
	vijaya lakshmi layout										
	1st Cross Road Ch:00-55	w0051		1		55.00	5.10	0.30	84.15		
	Cross Road Ch:00-55	w0055		1		55.00	5.10	0.30	84.15		
	Cross Road Ch:00-40	w0123		1		40.00	4.90	0.30	58.80		
	Cross Road Ch:00-60	w0051		1		60.00	4.60	0.30	82.80		
	3rd Cross Road Ch:00-85	w0077		1		85.00	4.30	0.30	109.65		
	4th Cross Road Ch:00-25	w0057		1		25.00	4.30	0.30	32.25		
	Ch:00-250 1st Main Road	w0106		1		250.00	5.40	0.30	405.00		
	Ch:00-250 MAA BEE Stores	w0114		1		250.00	5.10	0.30	382.50		
	1st Main Road Ch:00-183	w0073		1		183.00	4.00	0.30	219.60		
	1st Cross Road Ch:00-190	w0075		1		190.00	4.70	0.30	267.90		
	R O Plant Opp Road										
	R O Plant frant area			1		20.00	25.00	0.30	150.00		
	Ch:00-57	w0047		1		57.00	4.30	0.30	73.53		
	Ch:57-97	w0047		1		40.00	3.20	0.30	38.40		
	Ch:97-119	w0047		1		22.00	4.20	0.30	27.72		
	Ch:119-149	w0047		1		30.00	4.40	0.30	39.60		
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1		40.00	4.10	0.30	49.20		
	Ch:40-53	w0092		1		13.00	4.30	0.30	16.77		
	Ch:53-116	w0092		1		63.00	3.90	0.30	73.71		
	Ch:00-110 2nd Cross Road	w0098		1		110.00	4.30	0.30	141.90		
	Chikkasandra Village										
	Sapthgiri College Main Road RHS										
	Ch:0-100 4th Cross Road	w0839		1		100.00	4.50	0.30	135.00		
	Ch:0-122 3rd Cross Road	w0847		1		122.00	4.80	0.30	175.68		
	Ch:0-125 2nd Cross Road	w0843		1		125.00	5.00	0.30	187.50		
	Ch:0-120 5th Cross Road	w0853		1		120.00	5.30	0.30	190.80		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1		200.00	5.50	0.30	330.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1		40.00	4.00	0.30	48.00		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1		110.00	4.00	0.30	132.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1		160.00	4.50	0.30	216.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1		220.00	4.50	0.30	297.00		
	Ch:0-156 7th Cross Road	w0690		1		156.00	4.50	0.30	210.60		
	Ch:0-20 7th Cross Connecting Road			1		20.00	4.00	0.30	24.00		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1		115.00	5.00	0.30	172.50		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1		105.00	4.00	0.30	126.00		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1		100.00	4.00	0.30	120.00		
	Ch:100-283	w0883		1		183.00	5.50	0.30	301.95		
	CC Road										
	Medarahalli Village										
	LHS Road Elite Plams to Sri Swamy Bakery										
	Ch:00-82 2nd Cross Road	w0349		1		82.00	3.30	0.30	81.18		
	Ch:00-93 3rd Cross Road	w0343		1		93.00	3.80	0.30	106.02		

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:00-110 4th Cross Road	w0335		1	110.00	3.20	0.30	105.60		
	RHS Road Elite Plams to Sri Swamy Bakery									
	Ch:00-52 3rd Cross Road	w0347		1	52.00	3.70	0.30	57.72		
	Ch:00-52 4th Cross Road			1	52.00	3.50	0.30	54.60		
	Ch:00-40 5th Cross Road	w0341		1	40.00	3.50	0.30	42.00		
	Ch:40-177 5th Cross Road	w0341		1	137.00	3.80	0.30	156.18		
	Ch:00-42 6th Cross Road	w0337		1	42.00	3.50	0.30	44.10		
	Ch:42-86 6th Cross Road	w0337		1	44.00	3.50	0.30	46.20		
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-100 5th Cross Road	w0331		1	100.00	4.30	0.30	129.00		
	Ch:00-87 6th Cross Road	w0329		1	87.00	3.50	0.30	91.35		
	Ch:00-90 7th Cross Road Lakshmi Venkateshwara Wood Works	w0327		1	90.00	2.50	0.30	67.50		
	Shettihalli Village									
	Brindavana Layout									
	Ch: 00 -65 6th c/s road	w0946		1	65.00	3.50	0.30	68.25		
	Ch: 00 -100 5th c/s road	w0950		1	100.00	3.00	0.30	90.00		
	Ch: 00 -130 4th c/s road (Behtar store)	w0954		1	130.00	3.00	0.30	117.00		
	Ch: 00 -55 1st c/s road (Eskay hospital)	w1085		1	55.00	3.00	0.30	49.50		
	Ch: 00 -100 2nd c/s road	w0958		1	100.00	3.50	0.30	105.00		
	Kaveri Layout									
	Ch: 00 -80 1st c/s road	w0962		1	80.00	3.50	0.30	84.00		
	Ch: 00 -85 2nd c/s road	w0960		1	85.00	3.50	0.30	89.25		
	Ch: 00 -120 3rd c/s road	w0956		1	120.00	3.50	0.30	126.00		
	Ch: 00 -150 4th c/s road	w0944		1	150.00	3.50	0.30	157.50		
	Ch: 00 -180 5th c/s road	w0952		1	180.00	3.50	0.30	189.00		
	Ch: 00 -120 6th c/s road	w0942		1	120.00	3.50	0.30	126.00		
	Chikkasandra Village									
	Sapthgiri College Main Road RHS Roads									
	Ch:0-30 5th Cross Connecting road	w0851		1	30.00	3.40	0.30	30.60		
	Ch:0-145 Gokul Motors Beside Road	w0863		1	145.00	3.50	0.30	152.25		
	Ch:0-105 Sri Renukadevi Condiments Opp Road	w0875		1	105.00	5.00	0.30	157.50		
	Ch:0-110 6th Cross Road	w0696		1	110.00	5.00	0.30	165.00		
	Ch:0-120 5th Cross Road	w0702		1	120.00	5.50	0.30	198.00		
	Ch:0-116 4th Cross Road	w0704		1	116.00	5.00	0.30	174.00		
	Ch:0-109 2nd Cross Road	w0722		1	109.00	5.00	0.30	163.50		
	CH:0-20 1st Cross Road(Ankana House Front)	w0724		1	20.00	3.00	0.30	18.00		
	CH:20-109	w0724		1	89.00	4.50	0.30	120.15		
	Overly BC									
	Medarahalli Village									
	Pot Hole									
	Ch:00-510 Main Road Railway station track to Sunshine Public School	W0256		12	0.80	1.00	0.20	1.92		
	Road Cutting Across the Length									
	Ch:00-510 Main Road Railway station track to Sunshine Public School	W0256		12	5.50	0.80	0.20	10.56		
	AGB Layout									
	Across Road Cutting									
	Ch:00-770 60 feet road	w0737		30	9.00	0.30	0.20	16.20		
	Ch:00-170 12th Main Road	w0739		10	6.00	0.30	0.20	3.60		
	Ch:00-400 11th main road	w0660		22	6.50	0.30	0.20	8.58		
	Ch:00-260 Family Store Front Road	w0753		25	5.50	0.30	0.20	8.25		
	Pot Holes									
	Ch:00-770 60 feet road	w0737		25	0.80	1.00	0.20	4.00		
	Ch:00-170 12th Main Road	w0738		12	0.80	1.00	0.20	1.92		
	Ch:00-400 11th main road	w0660		21	0.80	1.00	0.20	3.36		
	Ch:00-260 Family Store Front Road	w0753		22	0.80	1.00	0.20	3.52		
	BWSSB Cutting			2	13513.00	0.80	0.40	8648.32		
							Total Qty	**36505.84**	**225.52**	**82,32,797.04**
3	Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 KPWD S.R 2018-19 It. No. 4.30 Pg.No. 13									
	New Culvert									

Sl. No	Description of Work	Road ID	Unit	No		Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
	bed		cum	45		6.50	1.20	0.15	52.65		
								Total Qty	**52.65**	**5619.79**	**2,95,882.13**
4	Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200										
	KPWD S.R 2018-19		It. No.			28.8.2	Pg.No.	229			
	New Culvert										
	One cubic mt 80kg For Culvert		T	1	1	9.76			9.76		
								Total Qty	**9.76**	**80146.60**	**7,82,230.82**
5	Providing and laying plain/reinforced cement concrete for side drains Wall & bottom thickness 15cm using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500,1700, 2200. including cost of materials, labour, HOM complete as per specifications.										
	KPWD S.R 2018-19		It. No.			37.59.2	Pg.No.	271			
	New Culvert										
	Raft		cum	45	1	6.50	1.05	0.20	61.43		
	Sidewall			45	2	6.50	0.23	0.45	60.55		
								Total Qty	**121.97**	**7422.99**	**9,05,381.99**
6	Providing and laying Pre Cast Drain Cover slabs of 230mm thick of mix M20 using graded granite jelly 20mm down size with steel reinforcement, including from work, lift charges, curing and concrete finished surfaces on both side etc. complete and as per drawing and direction of Engineer-in-charge of work (data Rate enclosed)										
	Approved Data Rate										
	New Culvert										
	New Culvert		sqm	45	1	6.50	1.00		292.50		
								Total Qty	**292.50**	**4486.00**	**13,12,155.00**
7	Providing granite slabs 7.5cms Thick of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.										
	KPWD S.R 2018-19		It. No.			5.31.1	Pg.No.	27			
	Missing/damaged slab										
	Qty vise It no 01		Sqm	1	1	7316.73			7316.73		
								Total Qty	**7316.73**	**742.00**	**54,29,013.66**
8	Providing and Fixing Pre cast covering Slab 100mm thick made out of CC, jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge.										
	Approved Data Rate										
	Missing/damaged slab										
	Qty vise It no 01		Sqm	1	1	868.50			868.50		
								Total Qty	**868.50**	**1922.00**	**16,69,257.00**
9	Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by mechanical means attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM complete as per specifications. Unloading and Lead for Disposal										
	KPWD S.R 2018-19		It. No.			19.56.	Pg.No.	146			
	LHS Road Sri Swamy Bakery to Raj Kaluve										
	Ch:00-140 Sun Sine School Front Road			1		140.00	6.00		840.00		
	Ch:00-130 G. Mukesh House Road			1		130.00	4.20		546.00		
	Ch:00-146 Sri Lakshmi Beside	w0271		1		146.00	4.50		657.00		
	Ch:00-38 Padma House Front Road			1		38.00	4.80		182.40		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1		25.00	4.00		100.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1		25.00	4.00		100.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1		86.00	5.00		430.00		
	RHS Road Raj Kaluve to Sri Swamy Bakery										
	Ch:00-105 Raja Kaluve Beside Road	w0265		1		105.00	4.70		493.50		
	Ch:00-122 Raunak Tower Beside Road	w0269		1		122.00	4.50		549.00		
	Ch:00-74 Athira House LHS Road			1		74.00	5.00		370.00		
	Ch:00-75 Athira House RHS Road			1		75.00	5.00		375.00		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1		115.00	5.00		575.00		
	railway station track to Dead End										

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:510-1130 Main Road Sunshine Public School to Dead End			1	620.00	5.60		3472.00		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-35 Mayura Bakery Front Road	w0229		1	35.00	4.00		140.00		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1	58.00	3.50		203.00		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-55 Manjushree Bakery Beside			1	55.00	5.00		275.00		
	Ch:00-57 Rusoil Bakery Beside			1	57.00	5.00		285.00		
	Ch:00-81 3rd Cross Road			1	81.00	5.00		405.00		
	Ch:00-73 RR Institution Road			1	73.00	5.00		365.00		
	Ch:00-70 Silver Spring International School Road			1	70.00	5.00		350.00		
	Ch:00-85 Siddeswara store Beside Road	w0206		1	85.00	4.00		340.00		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1	35.00	4.00		140.00		
	Ch:00-100 JMJ Provision Store	w0215		1	100.00	4.50		450.00		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1	62.00	4.00		248.00		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1	58.00	4.00		232.00		
	Ch:00-40 Coss Road			1	40.00	4.00		160.00		
	Ch:00-55 Sachith House Beside Road	w0210		1	55.00	4.00		220.00		
	Ch:00-144 Sachith House Front Road	w0204		1	144.00	4.00		576.00		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1	40.00	4.00		160.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		1	88.00	4.00		352.00		
	Ch:00-60 Virabramendra House Front Road	w0200		1	60.00	4.50		270.00		
	Ch:60-110	w0200		1	50.00	4.80		240.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		1	185.00	4.00		740.00		
	Ch:00-155 Kushi backery opp road	w0229		1	155.00	4.00		620.00		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1	120.00	4.00		480.00		
	Ch:00-40 Cross Road 1	w0225		1	40.00	4.00		160.00		
	Ch:00-56 Cross Road 2	w0231		1	56.00	4.00		224.00		
	Shettihalli Village									
	Ramakrishna Layout									
	Alladamara To Malasandara Road RHS Road									
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1	125.00	4.50		562.50		
	Ch:00-121 Pavana Nilaya Road	w0961		1	121.00	4.50		544.50		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1	68.00	4.50		306.00		
	Byraveshwara nagara									
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1	120.00	4.50		540.00		
	Ch:00-137 Park Beside Road	w0951		1	137.00	4.50		616.50		
	Ch:00-192 2nd Cross Road	w0943		1	192.00	4.50		864.00		
	Ch:00-195 3rd Cross Road	w0941		1	195.00	4.50		877.50		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1	110.00	4.50		495.00		
	Ch:00-120 Cross Road	w0935		1	120.00	4.00		480.00		
	Ch:00-130 Cross Road	w0937		1	130.00	4.00		520.00		
	A Y R Layout									
	Ch:00-110 Hotel Taste Beside Road			1	110.00	4.50		495.00		
	Ch:00-85 Saptagiri Nilaya	w0953		1	85.00	4.50		382.50		
	Ch:00-70 Padma Washing beside	w0813		1	70.00	4.50		315.00		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1	83.00	4.50		373.50		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1	85.00	4.50		382.50		
	Ch:00-90 Gurusai Front Road	w0823		1	90.00	4.50		405.00		
	Ch:00-95 Cross Road			1	95.00	4.50		427.50		
	AGB Layout									
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1	565.00	6.00		3390.00		
	Ch:00-100 3rd main Road	w0743		1	100.00	5.50		550.00		
	Ch:00-148 6th c/s Road	w0620		1	148.00	6.00		888.00		
	Ch:00-147 6th C Main Road	w0632		1	147.00	5.50		808.50		

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:00-130 11th Cross Road	w0741		1	130.00	5.50		715.00		
	Ch:00-127 13th c/s road	w0771		1	127.00	6.30		800.10		
	Ch:127-237 13th c/s Road	w0771		1	110.00	5.50		605.00		
	Ch:00-100 Divya apparel	w0682		1	100.00	5.20		520.00		
	Ch:00-160 Manasa school Road	w0630		1	160.00	5.50		880.00		
	Sidedahalli Village Village									
	Sampangiramaiah Layout									
	Ch:00-70 1st c\s road	w0418		1	70.00	4.80		336.00		
	Ch:00-205 c\s road 2	w0230		1	205.00	5.80		1189.00		
	Ch:00-167 2nd c\s road	w0215		1	167.00	5.20		868.40		
	Ch:00-140 c\s road 3	w0209		1	140.00	4.80		672.00		
	Ch:00- 126 c\s road 4	w0115		1	126.00	4.80		604.80		
	Kirloskar Layout									
	Ch:00-169 New trends	w0109		1	169.00	5.00		845.00		
	Ch:00-176 9th c\s road	w0101		1	176.00	5.20		915.20		
	Ch:00-125 3rd c\s road	w0202		1	125.00	6.00		750.00		
	Ch:00-129 4th c\s road	w0204		1	129.00	5.50		709.50		
	Ch:00-105 8th c\s road	w0103		1	105.00	5.00		525.00		
	Ch:00-65 6th c\s road	w0212		1	65.00	5.50		357.50		
	Ch:00-68 7th c\s road	w0105		1	68.00	5.00		340.00		
	Ch:00-105 5th c\s road	w0103		1	105.00	5.00		525.00		
	Ch:00-110 13th c\s road	w0214		1	110.00	5.00		550.00		
	Ch:00-72 14th c\s road	w0095		1	72.00	5.50		396.00		
	Ch:00-51 12th c\s road	w0210		1	51.00	4.50		229.50		
	Ch:00-121 11th c\s road	w0206		1	121.00	4.50		544.50		
	Ch:00-71 15th c\s road	w0093		1	71.00	4.20		298.20		
	Ch:00-121 10t c\s road	w0200		1	121.00	5.20		629.20		
	Ch:00-140 26th c\s road	w0174		1	140.00	5.00		700.00		
	Ch:00-113 27th c\s road	w0066		1	113.00	5.00		565.00		
	Ch:00-134 20thc\s road			1	134.00	5.20		696.80		
	Ch:00-129 25thc\s road	w0176		1	129.00	5.20		670.80		
	Ch:00-50 24th c\s road	w0180		1	50.00	5.00		250.00		
	Ch:00-254 22nd c\s road	w0190		1	254.00	5.20		1320.80		
	Ch:00-92 21st c\s road			1	92.00	5.00		460.00		
	Ch:00-150 28th c\s road	w0194		1	150.00	5.20		780.00		
	Abbigere Village									
	vijaya lakshmi layout									
	1st Cross Road Ch:00-55	w0051		1	55.00	5.10		280.50		
	Cross Road Ch:00-55	w0055		1	55.00	5.10		280.50		
	Cross Road Ch:00-40	w0123		1	40.00	4.90		196.00		
	Cross Road Ch:00-60	w0051		1	60.00	4.60		276.00		
	3rd Cross Road Ch:00-85	w0077		1	85.00	4.30		365.50		
	4th Cross Road Ch:00-25	w0057		1	25.00	4.30		107.50		
	Ch:00-250 1st Main Road	w0106		1	250.00	5.40		1350.00		
	Ch:00-250 MAA BEE Stores	w0114		1	250.00	5.10		1275.00		
	1st Main Road Ch:00-183	w0073		1	183.00	4.00		732.00		
	1st Cross Road Ch:00-190	w0075		1	190.00	4.70		893.00		
	R O Plant Opp Road									
	R O Plant frant area			1	20.00	6.00		120.00		
	Ch:00-57	w0047		1	57.00	4.30		245.10		
	Ch:57-97	w0047		1	40.00	3.20		128.00		
	Ch:97-119	w0047		1	22.00	4.20		92.40		
	Ch:119-149	w0047		1	30.00	4.40		132.00		
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1	40.00	4.10		164.00		
	Ch:40-53	w0092		1	13.00	4.30		55.90		
	Ch:53-116	w0092		1	63.00	3.90		245.70		
	Ch:00-110 2nd Cross Road	w0098		1	110.00	4.30		473.00		
	Chikkasandra Village									
	Sapthgiri College Main Road RHS Roads									
	Ch:0-100 4th Cross Road	w0839		1	100.00	4.50		450.00		
	Ch:0-122 3rd Cross Road	w0847		1	122.00	4.80		585.60		
	Ch:0-125 2nd Cross Road	w0843		1	125.00	5.00		625.00		
	Ch:0-120 5th Cross Road	w0853		1	120.00	5.30		636.00		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1	200.00	5.50		1100.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1	40.00	4.00		160.00		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1	110.00	4.00		440.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1	160.00	4.50		720.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1	220.00	4.50		990.00		
	Ch:0-156 7th Cross Road	w0690		1	156.00	4.50		702.00		

Sl. No	Description of Work	Road ID	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
	Ch:0-20 7th Cross Connecting Road			1	20.00	4.00		80.00		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1	115.00	5.00		575.00		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1	105.00	4.00		420.00		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1	100.00	4.00		400.00		
	Ch:100-283	w0883		1	183.00	5.50		1006.50		
								67098.90	**41.34**	**27,73,868.53**
	Leading charges for Scarified quantity		cum	1	67098.90		0.08	5367.91		
							Total Qty	**5367.91**	**30.72**	**1,64,902.20**
10	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceablandun serviceable materialsseperately complete as per specifications. KPWD S.R 2018-19 It. No. 18.47 Pg.No. 140									
	CC Road									
	Medarahalli Village									
	LHS Road Elite Plams to Sri Swamy Bakery									
	Ch:00-82 2nd Cross Road	w0349		1	82.00	1.00	0.15	12.30		
	Ch:00-110 4th Cross Road	w0335		1	110.00	1.20	0.15	19.80		
	RHS Road Elite Plams to Sri Swamy Bakery									
	Ch:00-52 3rd Cross Road	w0347		1	52.00	1.30	0.15	10.14		
	Ch:00-52 4th Cross Road			1	52.00	1.30	0.15	10.14		
	Ch:00-40 5th Cross Road	w0341		1	40.00	1.30	0.15	7.80		
	Ch:40-177 5th Cross Road	w0341		1	137.00	1.00	0.15	20.55		
	Ch:00-42 6th Cross Road	w0337		1	42.00	1.00	0.15	6.30		
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-100 5th Cross Road	w0331		1	100.00	1.20	0.15	18.00		
	Ch:00-87 6th Cross Road	w0329		1	87.00	1.20	0.15	15.66		
	Ch:00-90 7th Cross Road Lakshmi Venkateshwara Wood Works	w0327	cum	1	90.00	1.20	0.15	16.20		
	Shettihalli Village									
	Brindavana Layout									
	Ch: 00 -55 1st c/s road (Eskay hospital)			1	55.00	1.50	0.15	12.38		
	Ch: 00 -100 2nd c/s road	w0950		1	100.00	1.50	0.15	22.50		
	Kaveri Layout									
	Ch: 00 -80 1st c/s road	w0962		1	80.00	1.50	0.15	18.00		
	Ch: 00 -150 4th c/s road	w0944		1	150.00	1.50	0.15	33.75		
	Chikkasandra Village									
	Sapthgiri College Main Road RHS									
	Ch:0-145 Gokul Motors Beside Road	w0863		1	145.00	1.50	0.15	32.63		
	AGB Layout									
	Ch:127-234 13th c/s Road	w0771		1	107.00	4.00	0.15	64.20		
							Total Qty	**320.35**	**985.50**	**3,15,705.95**
11	Providing and filling Stone Dust in foundation to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications.									

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Data rate									
	BWSSB Cutting	cum	cum	2	13513.00	0.80	0.20	4324.16		
							Total Qty	**4324.16**	**1317.43**	**56,96,778.11**
12	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1,4.2									
	KPWD S.R 2018-19		lt. No.		4.20		Pg.No. 13			
	CC Road									
	Medarahalli Village									
	LHS Road Elite Plams to Sri Swamy Bakery									
	Ch:00-82 2nd Cross Road	w0349		1	82.00	3.30	0.10	27.06		
	Ch:00-93 3rd Cross Road	w0343		1	93.00	3.80	0.10	35.34		
	Ch:00-110 4th Cross Road	w0335		1	110.00	3.20	0.10	35.20		
	RHS Road Elite Plams to Sri Swamy Bakery									
	Ch:00-52 3rd Cross Road	w0347		1	52.00	3.70	0.10	19.24		
	Ch:00-52 4th Cross Road			1	52.00	3.50	0.10	18.20		
	Ch:00-40 5th Cross Road	w0341		1	40.00	3.50	0.10	14.00		
	Ch:40-177 5th Cross Road	w0341		1	137.00	3.80	0.10	52.06		
	Ch:00-42 6th Cross Road	w0337		1	42.00	3.50	0.10	14.70		
	Ch:42-86 6th Cross Road	w0337		1	44.00	3.50	0.10	15.40		
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-100 5th Cross Road	w0331		1	100.00	4.30	0.10	43.00		
	Ch:00-87 6th Cross Road	w0329		1	87.00	3.50	0.10	30.45		
	Ch:00-90 7th Cross Road Lakshmi Venkateshwara Wood Works	w0327		1	90.00	2.50	0.10	22.50		
	Shettihalli Village									
	Brindavana Layout									
	Ch: 00 -65 6th c/s road	w0946		1	65.00	3.50	0.10	22.75		
	Ch: 00 -100 5th c/s road	w0950		1	100.00	3.00	0.10	30.00		
	Ch: 00 -130 4th c/s road (Behtar store)	w0954	cum	1	130.00	3.00	0.10	39.00		
	Ch: 00 -55 1st c/s road (Eskay hospital)	w1085		1	55.00	3.00	0.10	16.50		
	Ch: 00 -100 2nd c/s road	w0958		1	100.00	3.50	0.10	35.00		
	Kaveri Layout									
	Ch: 00 -80 1st c/s road	w0962		1	80.00	3.50	0.10	28.00		
	Ch: 00 -85 2nd c/s road	w0960		1	85.00	3.50	0.10	29.75		
	Ch: 00 -120 3rd c/s road	w0956		1	120.00	3.50	0.10	42.00		
	Ch: 00 -150 4th c/s road	w0944		1	150.00	3.50	0.10	52.50		
	Ch: 00 -180 5th c/s road	w0952		1	180.00	3.50	0.10	63.00		
	Ch: 00 -120 6th c/s road	w0942		1	120.00	3.50	0.10	42.00		
	Chikkasandra Village									
	Sapthgiri College Main Road RHS Roads									
	Ch:0-30 5th Cross Connecting road	w0851		1	30.00	3.40	0.10	10.20		
	Ch:0-145 Gokul Motors Beside Road	w0863		1	145.00	3.50	0.10	50.75		
	Ch:0-105 Sri Renukadevi Condiments Opp Road	w0875		1	105.00	5.00	0.10	52.50		
	Ch:0-110 6th Cross Road	w0696		1	110.00	5.00	0.10	55.00		
	Ch:0-120 5th Cross Road	w0702		1	120.00	5.50	0.10	66.00		
	Ch:0-116 4th Cross Road	w0704		1	116.00	5.00	0.10	58.00		
	Ch:0-109 2nd Cross Road	w0722		1	109.00	5.00	0.10	54.50		
	CH:0-20 1st Cross Road(Ankana House Front)	w0724		1	20.00	3.00	0.10	6.00		
	CH:20-109	w0724		1	89.00	4.50	0.10	40.05		
							Total Qty	**1120.65**	**5505.64**	**61,69,895.47**

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
13	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 Its conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, soparation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications.									
	KPWD S.R 2018-19		lt. No.		22.6.1		Pg.No.	176		
	CC Road									
	Medarahalli Village									
	LHS Road Elite Plams to Sri Swamy Bakery									
	Ch:00-82 2nd Cross Road	w0349		1	82.00	3.30	0.15	40.59		
	Ch:00-93 3rd Cross Road	w0343		1	93.00	3.80	0.15	53.01		
	Ch:00-110 4th Cross Road	w0335		1	110.00	3.20	0.15	52.80		
	RHS Road Elite Plams to Sri Swamy Bakery									
	Ch:00-52 3rd Cross Road	w0347		1	52.00	3.70	0.15	28.86		
	Ch:00-52 4th Cross Road			1	52.00	3.50	0.15	27.30		
	Ch:00-40 5th Cross Road	w0341		1	40.00	3.50	0.15	21.00		
	Ch:40-177 5th Cross Road	w0341		1	137.00	3.80	0.15	78.09		
	Ch:00-42 6th Cross Road	w0337		1	42.00	3.50	0.15	22.05		
	Ch:42-86 6th Cross Road	w0337		1	44.00	3.50	0.15	23.10		
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-100 5th Cross Road	w0331		1	100.00	4.30	0.15	64.50		
	Ch:00-87 6th Cross Road	w0329		1	87.00	3.50	0.15	45.68		
	Ch:00-90 7th Cross Road Lakshmi Venkateshwara Wood Works	w0327		1	90.00	2.50	0.15	33.75		
	Shettihalli Village									
	Brindavana Layout									
	Ch: 00 -65 6th c/s road	w0946		1	65.00	3.50	0.15	34.13		
	Ch: 00 -100 5th c/s road	w0950		1	100.00	3.00	0.15	45.00		
	Ch: 00 -130 4th c/s road (Behtar store)	w0954	cum	1	130.00	3.00	0.15	58.50		
	Ch: 00 -55 1st c/s road (Eskay hospital)	w1085		1	55.00	3.00	0.15	24.75		
	Ch: 00 -100 2nd c/s road	w0958		1	100.00	3.50	0.15	52.50		
	Kaveri Layout									
	Ch: 00 -80 1st c/s road	w0962		1	80.00	3.50	0.15	42.00		
	Ch: 00 -85 2nd c/s road	w0960		1	85.00	3.50	0.15	44.63		
	Ch: 00 -120 3rd c/s road	w0956		1	120.00	3.50	0.15	63.00		
	Ch: 00 -150 4th c/s road	w0944		1	150.00	3.50	0.15	78.75		
	Ch: 00 -180 5th c/s road	w0952		1	180.00	3.50	0.15	94.50		
	Ch: 00 -120 6th c/s road	w0942		1	120.00	3.50	0.15	63.00		
	Chikkasandra Village									
	Sapthgiri College Main Road RHS Roads									
	Ch:0-30 5th Cross Connecting road	w0851		1	30.00	3.40	0.15	15.30		
	Ch:0-145 Gokul Motors Beside Road	w0863		1	145.00	3.50	0.15	76.13		
	Ch:0-105 Sri Renukadevi Condiments Opp Road	w0875		1	105.00	5.00	0.15	78.75		
	Ch:0-110 6th Cross Road	w0696		1	110.00	5.00	0.15	82.50		
	Ch:0-120 5th Cross Road	w0702		1	120.00	5.50	0.15	99.00		
	Ch:0-116 4th Cross Road	w0704		1	116.00	5.00	0.15	87.00		
	Ch:0-109 2nd Cross Road	w0722		1	109.00	5.00	0.15	81.75		
	CH:0-20 1st Cross Road(Ankana House Front)	w0724		1	20.00	3.00	0.15	9.00		
	CH:20-109	w0724		1	89.00	4.50	0.15	60.08		
							Total Qty	**1680.98**	**5634.31**	**94,71,162.42**
14	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregatesof granite/trap/basalt material, mixing by mix in place method by rotavator at OMC, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications.Clause 401 of MORTH V Revision..									
	KPWD S.R 2018-19		lt. No.		20.50		Pg.No.	153		
	Medarahalli Village									

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	LHS Road Sri Swamy Bakery to Raj Kaluve										
	Ch:00-140 Sun Sine School Front Road			1		140.00	6.00	0.15	126.00		
	Ch:00-130 G. Mukesh House Road			1		130.00	4.20	0.15	81.90		
	Ch:00-146 Sri Lakshmi Beside	w0271		1		146.00	4.50	0.15	98.55		
	Ch:00-38 Padma House Front Road			1		38.00	4.80	0.15	27.36		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1		25.00	4.00	0.15	15.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1		25.00	4.00	0.15	15.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1		86.00	5.00	0.15	64.50		
	RHS Road Raj Kaluve to Sri Swamy Bakery										
	Ch:00-105 Raja Kaluve Beside Road	w0265		1		105.00	4.70	0.15	74.03		
	Ch:00-122 Raunak Tower Beside Road	w0269		1		122.00	4.50	0.15	82.35		
	Ch:00-74 Athira House LHS Road			1		74.00	5.00	0.15	55.50		
	Ch:00-75 Athira House RHS Road			1		75.00	5.00	0.15	56.25		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1		115.00	5.00	0.15	86.25		
	railway station track to Dead End										
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		1		620.00	5.60	0.15	520.80		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-35 Mayura Bakery Front Road	w0258		1		35.00	4.00	0.15	21.00		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1		58.00	3.50	0.15	30.45		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-55 Manjushree Bakery Beside	w0267		1		55.00	5.00	0.15	41.25		
	Ch:00-57 Rusoil Bakery Beside	w0255		1		57.00	5.00	0.15	42.75		
	Ch:00-81 3rd Cross Road	w0253		1		81.00	5.00	0.15	60.75		
	Ch:00-73 RR Institution Road	w0251		1		73.00	5.00	0.15	54.75		
	Ch:00-70 Silver Spring International School Road	w0247		1		70.00	5.00	0.15	52.50		
	Ch:00-85 Siddeswara store Beside Road	w0206		1		85.00	4.00	0.15	51.00		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1		35.00	4.00	0.15	21.00		
	Ch:00-100 JMJ Provision Store	w0215		1		100.00	4.50	0.15	67.50		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1		62.00	4.00	0.15	37.20		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1		58.00	4.00	0.15	34.80		
	Ch:00-40 Coss Road			1		40.00	4.00	0.15	24.00		
	Ch:00-55 Sachith House Beside Road	w0210		1		55.00	4.00	0.15	33.00		
	Ch:00-144 Sachith House Front Road	w0204		1		144.00	4.00	0.15	86.40		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1		40.00	4.00	0.15	24.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		1		88.00	4.00	0.15	52.80		
	Ch:00-60 Virabramendra House Front Road	w0200		1		60.00	4.50	0.15	40.50		
	Ch:60-110	w0200		1		50.00	4.80	0.15	36.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		1		185.00	4.00	0.15	111.00		
	Ch:00-155 Kushi backery opp road	w0229		1		155.00	4.00	0.15	93.00		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1		120.00	4.00	0.15	72.00		
	Ch:00-40 Cross Road 1	w0225		1		40.00	4.00	0.15	24.00		
	Ch:00-56 Cross Road 2	w0231		1		56.00	4.00	0.15	33.60		
	Shettihalli Village										
	Ramakrishna Layout										
	Alladamara To Malasandara Road RHS Road										
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1		125.00	4.50	0.15	84.38		
	Ch:00-121 Pavana Nilaya Road	w0961		1		121.00	4.50	0.15	81.68		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1		68.00	4.50	0.15	45.90		
	Byraveshwara nagara										
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1		120.00	4.50	0.15	81.00		
	Ch:00-137 Park Beside Road	w0951		1		137.00	4.50	0.15	92.48		
	Ch:00-192 2nd Cross Road	w0943		1		192.00	4.50	0.15	129.60		
	Ch:00-195 3rd Cross Road	w0941		1		195.00	4.50	0.15	131.63		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1		110.00	4.50	0.15	74.25		
	Ch:00-120 Cross Road	w0935		1		120.00	4.00	0.15	72.00		
	Ch:00-130 Cross Road	w0937		1		130.00	4.00	0.15	78.00		
	A Y R Layout										
	Ch:00-110 Hotel Taste Beside Road			1		110.00	4.50	0.15	74.25		
	Ch:00-85 Saptagiri Nilaya	w0953		1		85.00	4.50	0.15	57.38		
	Ch:00-70 Padma Washing beside	w0813		1		70.00	4.50	0.15	47.25		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1		83.00	4.50	0.15	56.03		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1		85.00	4.50	0.15	57.38		
	Ch:00-90 Gurusai Front Road	w0823		1		90.00	4.50	0.15	60.75		
	Ch:00-95 Cross Road			1		95.00	4.50	0.15	64.13		
			Sqm								
	AGB Layout										
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1		565.00	6.00	0.15	508.50		
	Ch:00-100 3rd main Road	w0743		1		100.00	5.50	0.15	82.50		
	Ch:00-148 6th c/s Road	w0620		1		148.00	6.00	0.15	133.20		
	Ch:00-147 6th C Main Road	w0632		1		147.00	5.50	0.15	121.28		
	Ch:00-130 11th Cross Road	w0741		1		130.00	5.50	0.15	107.25		
	Ch:00-127 13th c/s road			1		127.00	6.30	0.15	120.02		
	Ch:127-237 13th c/s Road			1		110.00	5.50	0.15	90.75		
	Ch:00-100 Divya apparel	w0682		1		100.00	5.20	0.15	78.00		
	Ch:00-160 Manasa school Road	w0630		1		160.00	5.50	0.15	132.00		
	Sidedahalli Village Village										
	Sampangiramaiah Layout										
	Ch:00-70 1st c\s road	w0418		1		70.00	4.80	0.15	50.40		
	Ch:00-205 c\s road 2	w0230		1		205.00	5.80	0.15	178.35		
	Ch:00-167 2nd c\s road	w0215		1		167.00	5.20	0.15	130.26		
	Ch:00-140 c\s road 3	w0209		1		140.00	4.80	0.15	100.80		
	Ch:00- 126 c\s road 4	w0115		1		126.00	4.80	0.15	90.72		
	Kirloskar Layout										
	Ch:00-169 New trends	w0109		1		169.00	5.00	0.15	126.75		
	Ch:00-176 9th c\s road	w0101		1		176.00	5.20	0.15	137.28		
	Ch:00-125 3rd c\s road	w0202		1		125.00	6.00	0.15	112.50		
	Ch:00-129 4th c\s road	w0204		1		129.00	5.50	0.15	106.43		
	Ch:00-105 8th c\s road	w0103		1		105.00	5.00	0.15	78.75		
	Ch:00-65 6th c\s road	w0212		1		65.00	5.50	0.15	53.63		
	Ch:00-68 7th c\s road	w0105		1		68.00	5.00	0.15	51.00		
	Ch:00-105 5th c\s road	w0103		1		105.00	5.00	0.15	78.75		
	Ch:00-110 13th c\s road	w0214		1		110.00	5.00	0.15	82.50		
	Ch:00-72 14th c\s road	w0095		1		72.00	5.50	0.15	59.40		
	Ch:00-51 12th c\s road	w0210		1		51.00	4.50	0.15	34.43		
	Ch:00-121 11th c\s road	w0206		1		121.00	4.50	0.15	81.68		
	Ch:00-71 15th c\s road	w0093		1		71.00	4.20	0.15	44.73		
	Ch:00-121 10t c\s road	w0200		1		121.00	5.20	0.15	94.38		
	Ch:00-140 26th c\s road	w0174		1		140.00	5.00	0.15	105.00		
	Ch:00-113 27th c\s road	w0066		1		113.00	5.00	0.15	84.75		
	Ch:00-134 20thc\s road			1		134.00	5.20	0.15	104.52		
	Ch:00-129 25thc\s road	w0176		1		129.00	5.20	0.15	100.62		
	Ch:00-50 24th c\s road	w0180		1		50.00	5.00	0.15	37.50		
	Ch:00-254 22nd c\s road	w0190		1		254.00	5.20	0.15	198.12		
	Ch:00-92 21st c\s road			1		92.00	5.00	0.15	69.00		
	Ch:00-150 28th c\s road	w0194		1		150.00	5.20	0.15	117.00		
	Abbigere Village										
	vijaya lakshmi layout										
	1st Cross Road Ch:00-55	w0051		1		55.00	5.10	0.15	42.08		
	Cross Road Ch:00-55	w0055		1		55.00	5.10	0.15	42.08		
	Cross Road Ch:00-40	w0123		1		40.00	4.90	0.15	29.40		
	Cross Road Ch:00-60	w0051		1		60.00	4.60	0.15	41.40		
	3rd Cross Road Ch:00-85	w0077		1		85.00	4.30	0.15	54.83		
	4th Cross Road Ch:00-25	w0057		1		25.00	4.30	0.15	16.13		
	Ch:00-250 1st Main Road	w0106		1		250.00	5.40	0.15	202.50		
	Ch:00-250 MAA BEE Stores	w0114		1		250.00	5.10	0.15	191.25		
	1st Main Road Ch:00-183	w0073		1		183.00	4.00	0.15	109.80		
	1st Cross Road Ch:00-190	w0075		1		190.00	4.70	0.15	133.95		
	R O Plant Opp Road										
	R O Plant frant area			1		20.00	25.00	0.15	75.00		
	Ch:00-57	w0047		1		57.00	4.30	0.15	36.77		
	Ch:57-97	w0047		1		40.00	3.20	0.15	19.20		
	Ch:97-119	w0047		1		22.00	4.20	0.15	13.86		
	Ch:119-149	w0047		1		30.00	4.40	0.15	19.80		

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1	40.00	4.10	0.15	24.60		
	Ch:40-53	w0092		1	13.00	4.30	0.15	8.39		
	Ch:53-116	w0092		1	63.00	3.90	0.15	36.86		
	Ch:00-110 2nd Cross Road	w0098		1	110.00	4.30	0.15	70.95		
	Chikkasandra Village									
	Sapthgiri College Main Road RHS Roads									
	Ch:0-100 4th Cross Road	w0839		1	100.00	4.50	0.15	67.50		
	Ch:0-122 3rd Cross Road	w0847		1	122.00	4.80	0.15	87.84		
	Ch:0-125 2nd Cross Road	w0843		1	125.00	5.00	0.15	93.75		
	Ch:0-120 5th Cross Road	w0853		1	120.00	5.30	0.15	95.40		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1	200.00	5.50	0.15	165.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1	40.00	4.00	0.15	24.00		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1	110.00	4.00	0.15	66.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1	160.00	4.50	0.15	108.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1	220.00	4.50	0.15	148.50		
	Ch:0-156 7th Cross Road	w0690		1	156.00	4.50	0.15	105.30		
	Ch:0-20 7th Cross Connecting Road			1	20.00	4.00	0.15	12.00		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1	115.00	5.00	0.15	86.25		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1	105.00	4.00	0.15	63.00		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1	100.00	4.00	0.15	60.00		
	Ch:100-283	w0883		1	183.00	5.50	0.15	150.98		
							Total Qty	**10121.84**	**1994.92**	**2,01,92,261.05**
15	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406									
	KPWD S.R 2018-19		It. No.		20.18		Pg.No.	155		
	New BC Road									
	Medarahalli Village									
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-140 Sun Sine School Front Road			1	140.00	6.00	0.20	168.00		
	Ch:00-130 G. Mukesh House Road			1	130.00	4.20	0.20	109.20		
	Ch:00-146 Sri Lakshmi Beside	w0271		1	146.00	4.50	0.20	131.40		
	Ch:00-38 Padma House Front Road			1	38.00	4.80	0.20	36.48		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1	25.00	4.00	0.20	20.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1	25.00	4.00	0.20	20.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1	86.00	5.00	0.20	86.00		
	RHS Road Raj Kaluve to Sri Swamy Bakery									
	Ch:00-105 Raja Kaluve Beside Road	w0265		1	105.00	4.70	0.20	98.70		
	Ch:00-122 Raunak Tower Beside Road	w0269		1	122.00	4.50	0.20	109.80		
	Ch:00-74 Athira House LHS Road			1	74.00	5.00	0.20	74.00		
	Ch:00-75 Athira House RHS Road			1	75.00	5.00	0.20	75.00		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1	115.00	5.00	0.20	115.00		
	railway station track to Dead End									
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		1	620.00	5.60	0.20	694.40		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-35 Mayura Bakery Front Road	w0258		1	35.00	4.00	0.20	28.00		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1	58.00	3.50	0.20	40.60		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-55 Manjushree Bakery Beside	w0267		1	55.00	5.00	0.20	55.00		
	Ch:00-57 Rusoil Bakery Beside	w0255		1	57.00	5.00	0.20	57.00		
	Ch:00-81 3rd Cross Road	w0253		1	81.00	5.00	0.20	81.00		
	Ch:00-73 RR Institution Road	w0251		1	73.00	5.00	0.20	73.00		
	Ch:00-70 Silver Spring International School Road	w0247		1	70.00	5.00	0.20	70.00		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-85 Siddeswara store Beside Road	w0206		1		85.00	4.00	0.20	68.00		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1		35.00	4.00	0.20	28.00		
	Ch:00-100 JMJ Provision Store	w0215		1		100.00	4.50	0.20	90.00		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1		62.00	4.00	0.20	49.60		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1		58.00	4.00	0.20	46.40		
	Ch:00-40 Coss Road			1		40.00	4.00	0.20	32.00		
	Ch:00-55 Sachith House Beside Road	w0210		1		55.00	4.00	0.20	44.00		
	Ch:00-144 Sachith House Front Road	w0204		1		144.00	4.00	0.20	115.20		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1		40.00	4.00	0.20	32.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		1		88.00	4.00	0.20	70.40		
	Ch:00-60 Virabramendra House Front Road	w0200		1		60.00	4.50	0.20	54.00		
	Ch:60-110	w0200		1		50.00	4.80	0.20	48.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		1		185.00	4.00	0.20	148.00		
	Ch:00-155 Kushi backery opp road	w0229		1		155.00	4.00	0.20	124.00		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1		120.00	4.00	0.20	96.00		
	Ch:00-40 Cross Road 1	w0225		1		40.00	4.00	0.20	32.00		
	Ch:00-56 Cross Road 2	w0231		1		56.00	4.00	0.20	44.80		
	Shettihalli Village										
	Ramakrishna Layout										
	Alladamara To Malasandara Road RHS Road										
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1		125.00	4.50	0.20	112.50		
	Ch:00-121 Pavana Nilaya Road	w0961		1		121.00	4.50	0.20	108.90		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1		68.00	4.50	0.20	61.20		
	Byraveshwara nagara										
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1		120.00	4.50	0.20	108.00		
	Ch:00-137 Park Beside Road	w0951		1		137.00	4.50	0.20	123.30		
	Ch:00-192 2nd Cross Road	w0943		1		192.00	4.50	0.20	172.80		
	Ch:00-195 3rd Cross Road	w0941		1		195.00	4.50	0.20	175.50		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1		110.00	4.50	0.20	99.00		
	Ch:00-120 Cross Road	w0935		1		120.00	4.00	0.20	96.00		
	Ch:00-130 Cross Road	w0937		1		130.00	4.00	0.20	104.00		
	A Y R Layout										
	Ch:00-110 Hotel Taste Beside Road			1		110.00	4.50	0.20	99.00		
	Ch:00-85 Saptagiri Nilaya	w0953		1		85.00	4.50	0.20	76.50		
	Ch:00-70 Padma Washing beside	w0813		1		70.00	4.50	0.20	63.00		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1		83.00	4.50	0.20	74.70		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1		85.00	4.50	0.20	76.50		
	Ch:00-90 Gurusai Front Road	w0823		1		90.00	4.50	0.20	81.00		
	Ch:00-95 Cross Road			1		95.00	4.50	0.20	85.50		
	AGB Layout										
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1		565.00	6.00	0.20	678.00		
	Ch:00-100 3rd main Road	w0743		1		100.00	5.50	0.20	110.00		
	Ch:00-148 6th c/s Road	w0620		1		148.00	6.00	0.20	177.60		
	Ch:00-147 6th C Main Road	w0632		1		147.00	5.50	0.20	161.70		
	Ch:00-130 11th Cross Road	w0741		1		130.00	5.50	0.20	143.00		
	Ch:00-127 13th c/s road			1		127.00	6.30	0.20	160.02		
	Ch:127-237 13th c/s Road			1		110.00	5.50	0.20	121.00		
	Ch:00-100 Divya apparel	w0682		1		100.00	5.20	0.20	104.00		
	Ch:00-160 Manasa school Road	w0630		1		160.00	5.50	0.20	176.00		
			cum								
	Sidedahalli Village Village										
	Sampangiramaiah Layout										
	Ch:00-70 1st c\s road	w0418		1		70.00	4.80	0.20	67.20		
	Ch:00-205 c\s road 2	w0230		1		205.00	5.80	0.20	237.80		
	Ch:00-167 2nd c\s road	w0215		1		167.00	5.20	0.20	173.68		
	Ch:00-140 c\s road 3	w0209		1		140.00	4.80	0.20	134.40		
	Ch:00- 126 c\s road 4	w0115		1		126.00	4.80	0.20	120.96		
	Kirloskar Layout										
	Ch:00-169 New trends	w0109		1		169.00	5.00	0.20	169.00		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-176 9th c\s road	w0101		1		176.00	5.20	0.20	183.04		
	Ch:00-125 3rd c\s road	w0202		1		125.00	6.00	0.20	150.00		
	Ch:00-129 4th c\s road	w0204		1		129.00	5.50	0.20	141.90		
	Ch:00-105 8th c\s road	w0103		1		105.00	5.00	0.20	105.00		
	Ch:00-65 6th c\s road	w0212		1		65.00	5.50	0.20	71.50		
	Ch:00-68 7th c\s road	w0105		1		68.00	5.00	0.20	68.00		
	Ch:00-105 5th c\s road	w0103		1		105.00	5.00	0.20	105.00		
	Ch:00-110 13th c\s road	w0214		1		110.00	5.00	0.20	110.00		
	Ch:00-72 14th c\s road	w0095		1		72.00	5.50	0.20	79.20		
	Ch:00-51 12th c\s road	w0210		1		51.00	4.50	0.20	45.90		
	Ch:00-121 11th c\s road	w0206		1		121.00	4.50	0.20	108.90		
	Ch:00-71 15th c\s road	w0093		1		71.00	4.20	0.20	59.64		
	Ch:00-121 10t c\s road	w0200		1		121.00	5.20	0.20	125.84		
	Ch:00-140 26th c\s road	w0174		1		140.00	5.00	0.20	140.00		
	Ch:00-113 27th c\s road	w0066		1		113.00	5.00	0.20	113.00		
	Ch:00-134 20thc\s road			1		134.00	5.20	0.20	139.36		
	Ch:00-129 25thc\s road	w0176		1		129.00	5.20	0.20	134.16		
	Ch:00-50 24th c\s road	w0180		1		50.00	5.00	0.20	50.00		
	Ch:00-254 22nd c\s road	w0190		1		254.00	5.20	0.20	264.16		
	Ch:00-92 21st c\s road			1		92.00	5.00	0.20	92.00		
	Ch:00-150 28th c\s road	w0194		1		150.00	5.20	0.20	156.00		
	Abbigere Village										
	vijaya lakshmi layout										
	1st Cross Road Ch:00-55	w0051		1		55.00	5.10	0.20	56.10		
	Cross Road Ch:00-55	w0055		1		55.00	5.10	0.20	56.10		
	Cross Road Ch:00-40	w0123		1		40.00	4.90	0.20	39.20		
	Cross Road Ch:00-60	w0051		1		60.00	4.60	0.20	55.20		
	3rd Cross Road Ch:00-85	w0077		1		85.00	4.30	0.20	73.10		
	4th Cross Road Ch:00-25	w0057		1		25.00	4.30	0.20	21.50		
	Ch:00-250 1st Main Road	w0106		1		250.00	5.40	0.20	270.00		
	Ch:00-250 MAA BEE Stores	w0114		1		250.00	5.10	0.20	255.00		
	1st Main Road Ch:00-183	w0073		1		183.00	4.00	0.20	146.40		
	1st Cross Road Ch:00-190	w0075		1		190.00	4.70	0.20	178.60		
	R O Plant Opp Road										
	R O Plant frant area			1		20.00	25.00	0.20	100.00		
	Ch:00-57	w0047		1		57.00	4.30	0.20	49.02		
	Ch:57-97	w0047		1		40.00	3.20	0.20	25.60		
	Ch:97-119	w0047		1		22.00	4.20	0.20	18.48		
	Ch:119-149	w0047		1		30.00	4.40	0.20	26.40		
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1		40.00	4.10	0.20	32.80		
	Ch:40-53	w0092		1		13.00	4.30	0.20	11.18		
	Ch:53-116	w0092		1		63.00	3.90	0.20	49.14		
	Ch:00-110 2nd Cross Road	w0098		1		110.00	4.30	0.20	94.60		
	Chikkasandra Village										
	Sapthgiri College Main Road RHS Roads										
	Ch:0-100 4th Cross Road	w0839		1		100.00	4.50	0.20	90.00		
	Ch:0-122 3rd Cross Road	w0847		1		122.00	4.80	0.20	117.12		
	Ch:0-125 2nd Cross Road	w0843		1		125.00	5.00	0.20	125.00		
	Ch:0-120 5th Cross Road	w0853		1		120.00	5.30	0.20	127.20		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1		200.00	5.50	0.20	220.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1		40.00	4.00	0.20	32.00		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1		110.00	4.00	0.20	88.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1		160.00	4.50	0.20	144.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1		220.00	4.50	0.20	198.00		
	Ch:0-156 7th Cross Road	w0690		1		156.00	4.50	0.20	140.40		
	Ch:0-20 7th Cross Connecting Road			1		20.00	4.00	0.20	16.00		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1		115.00	5.00	0.20	115.00		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1		105.00	4.00	0.20	84.00		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1		100.00	4.00	0.20	80.00		
	Ch:100-283	w0883		1		183.00	5.50	0.20	201.30		
	Overly BC										
	Medarahalli Village										
	Pot Hole										
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		12		0.80	1.00	0.20	1.92		
	Road Cutting Across the Length										

Sl. No	Description of Work	Road ID	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		12	5.50	0.80	0.20	10.56		
	AGB Layout									
	Across Road Cutting									
	Ch:00-770 60 feet road	w0737		30	9.00	0.30	0.20	16.20		
	Ch:00-170 12th Main Road	w0739		10	6.00	0.30	0.20	3.60		
	Ch:00-400 11th main road	w0660		22	6.50	0.30	0.20	8.58		
	Ch:00-260 Family Store Front Road	w0753		25	5.50	0.30	0.20	8.25		
	Pot Holes									
	Ch:00-770 60 feet road	w0737		25	0.80	1.00	0.20	4.00		
	Ch:00-170 12th Main Road	w0738		12	0.80	1.00	0.20	1.92		
	Ch:00-400 11th main road	w0660		21	0.80	1.00	0.20	3.36		
	Ch:00-260 Family Store Front Road	w0753		22	0.80	1.00	0.20	3.52		
	BWSSB Cutting			2	13513.00	0.80	0.20	4324.16		
							Total Qty	**17881.85**	**2001.28**	**3,57,86,588.77**
16	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM complete as per specifications. Clause 501 of MORTH V revision KPWD S.R 2018-19 It. No. 21.2. Pg.No. 158									
	Medarahalli Village									
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		1	510.00	6.00		3060.00		
	AGB Layout									
	Ch:00-770 60 feet road	w0737		1	770.00	9.00		6930.00		
	Ch:00-170 12th Main Road	w0739		1	170.00	6.00		1020.00		
	Ch:00-400 11th main road	w0660		1	400.00	6.50		2600.00		
	Ch:00-260 Family Store Front Road	w0753		1	260.00	5.50		1430.00		
							Total Qty	**15040.00**	**5.30**	**79,712.00**
17	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications.Clause 502 of MORTH V revision KPWD S.R 2018-19 It. No. 21.60 Pg.No. 158									
	New BC Road									
	Medarahalli Village									
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-140 Sun Sine School Front Road			1	140.00	6.00		840.00		
	Ch:00-130 G. Mukesh House Road			1	130.00	4.20		546.00		
	Ch:00-146 Sri Lakshmi Beside	w0271		1	146.00	4.50		657.00		
	Ch:00-38 Padma House Front Road			1	38.00	4.80		182.40		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1	25.00	4.00		100.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1	25.00	4.00		100.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1	86.00	5.00		430.00		
	RHS Road Raj Kaluve to Sri Swamy Bakery									
	Ch:00-105 Raja Kaluve Beside Road	w0265		1	105.00	4.70		493.50		
	Ch:00-122 Raunak Tower Beside Road	w0269		1	122.00	4.50		549.00		
	Ch:00-74 Athira House LHS Road			1	74.00	5.00		370.00		
	Ch:00-75 Athira House RHS Road			1	75.00	5.00		375.00		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1	115.00	5.00		575.00		
	railway station track to Dead End									
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		1	620.00	5.60		3472.00		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-35 Mayura Bakery Front Road	w0258		1	35.00	4.00		140.00		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1	58.00	3.50		203.00		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-55 Manjushree Bakery Beside	w0267		1	55.00	5.00		275.00		
	Ch:00-57 Rusoil Bakery Beside	w0255		1	57.00	5.00		285.00		
	Ch:00-81 3rd Cross Road	w0253		1	81.00	5.00		405.00		
	Ch:00-73 RR Institution Road	w0251		1	73.00	5.00		365.00		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-70 Silver Spring International School Road	w0247		1		70.00	5.00		350.00		
	Ch:00-85 Siddeswara store Beside Road	w0206		1		85.00	4.00		340.00		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1		35.00	4.00		140.00		
	Ch:00-100 JMJ Provision Store	w0215		1		100.00	4.50		450.00		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1		62.00	4.00		248.00		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1		58.00	4.00		232.00		
	Ch:00-40 Coss Road			1		40.00	4.00		160.00		
	Ch:00-55 Sachith House Beside Road	w0210		1		55.00	4.00		220.00		
	Ch:00-144 Sachith House Front Road	w0204		1		144.00	4.00		576.00		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1		40.00	4.00		160.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		1		88.00	4.00		352.00		
	Ch:00-60 Virabramendra House Front Road	w0200		1		60.00	4.50		270.00		
	Ch:60-110	w0200		1		50.00	4.80		240.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		1		185.00	4.00		740.00		
	Ch:00-155 Kushi backery opp road	w0229		1		155.00	4.00		620.00		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1		120.00	4.00		480.00		
	Ch:00-40 Cross Road 1	w0225		1		40.00	4.00		160.00		
	Ch:00-56 Cross Road 2	w0231		1		56.00	4.00		224.00		
	Shettihalli Village										
	Ramakrishna Layout										
	Alladamara To Malasandara Road RHS Road										
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1		125.00	4.50		562.50		
	Ch:00-121 Pavana Nilaya Road	w0961		1		121.00	4.50		544.50		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1		68.00	4.50		306.00		
	Byraveshwara nagara										
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1		120.00	4.50		540.00		
	Ch:00-137 Park Beside Road	w0951		1		137.00	4.50		616.50		
	Ch:00-192 2nd Cross Road	w0943		1		192.00	4.50		864.00		
	Ch:00-195 3rd Cross Road	w0941		1		195.00	4.50		877.50		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1		110.00	4.50		495.00		
	Ch:00-120 Cross Road	w0935		1		120.00	4.00		480.00		
	Ch:00-130 Cross Road	w0937		1		130.00	4.00		520.00		
	A Y R Layout										
	Ch:00-110 Hotel Taste Beside Road			1		110.00	4.50		495.00		
	Ch:00-85 Saptagiri Nilaya	w0953		1		85.00	4.50		382.50		
	Ch:00-70 Padma Washing beside	w0813		1		70.00	4.50		315.00		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1		83.00	4.50		373.50		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1		85.00	4.50		382.50		
	Ch:00-90 Gurusai Front Road	w0823		1		90.00	4.50		405.00		
	Ch:00-95 Cross Road			1		95.00	4.50		427.50		
	AGB Layout										
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1		565.00	6.00		3390.00		
	Ch:00-100 3rd main Road	w0743		1		100.00	5.50		550.00		
	Ch:00-148 6th c/s Road	w0620		1		148.00	6.00		888.00		
	Ch:00-147 6th C Main Road	w0632		1		147.00	5.50		808.50		
	Ch:00-130 11th Cross Road	w0741		1		130.00	5.50		715.00		
	Ch:00-127 13th c/s road			1		127.00	6.30		800.10		
	Ch:127-237 13th c/s Road			1		110.00	5.50		605.00		
	Ch:00-100 Divya apparel	w0682		1		100.00	5.20		520.00		
	Ch:00-160 Manasa school Road	w0630		1		160.00	5.50		880.00		
			Sqm								
	Sidedahalli Village Village										
	Sampangiramaiah Layout										
	Ch:00-70 1st c\s road	w0418		1		70.00	4.80		336.00		
	Ch:00-205 c\s road 2	w0230		1		205.00	5.80		1189.00		
	Ch:00-167 2nd c\s road	w0215		1		167.00	5.20		868.40		
	Ch:00-140 c\s road 3	w0209		1		140.00	4.80		672.00		
	Ch:00- 126 c\s road 4	w0115		1		126.00	4.80		604.80		

Sl. No	Description of Work	Road ID	Unit	No		Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
	Kirloskar Layout										
	Ch:00-169 New trends	w0109		1		169.00	5.00		845.00		
	Ch:00-176 9th c\s road	w0101		1		176.00	5.20		915.20		
	Ch:00-125 3rd c\s road	w0202		1		125.00	6.00		750.00		
	Ch:00-129 4th c\s road	w0204		1		129.00	5.50		709.50		
	Ch:00-105 8th c\s road	w0103		1		105.00	5.00		525.00		
	Ch:00-65 6th c\s road	w0212		1		65.00	5.50		357.50		
	Ch:00-68 7th c\s road	w0105		1		68.00	5.00		340.00		
	Ch:00-105 5th c\s road	w0103		1		105.00	5.00		525.00		
	Ch:00-110 13th c\s road	w0214		1		110.00	5.00		550.00		
	Ch:00-72 14th c\s road	w0095		1		72.00	5.50		396.00		
	Ch:00-51 12th c\s road	w0210		1		51.00	4.50		229.50		
	Ch:00-121 11th c\s road	w0206		1		121.00	4.50		544.50		
	Ch:00-71 15th c\s road	w0093		1		71.00	4.20		298.20		
	Ch:00-121 10t c\s road	w0200		1		121.00	5.20		629.20		
	Ch:00-140 26th c\s road	w0174		1		140.00	5.00		700.00		
	Ch:00-113 27th c\s road	w0066		1		113.00	5.00		565.00		
	Ch:00-134 20thc\s road			1		134.00	5.20		696.80		
	Ch:00-129 25thc\s road	w0176		1		129.00	5.20		670.80		
	Ch:00-50 24th c\s road	w0180		1		50.00	5.00		250.00		
	Ch:00-254 22nd c\s road	w0190		1		254.00	5.20		1320.80		
	Ch:00-92 21st c\s road			1		92.00	5.00		460.00		
	Ch:00-150 28th c\s road	w0194		1		150.00	5.20		780.00		
	Abbigere Village										
	vijaya lakshmi layout										
	1st Cross Road Ch:00-55	w0051		1		55.00	5.10		280.50		
	Cross Road Ch:00-55	w0055		1		55.00	5.10		280.50		
	Cross Road Ch:00-40	w0123		1		40.00	4.90		196.00		
	Cross Road Ch:00-60	w0051		1		60.00	4.60		276.00		
	3rd Cross Road Ch:00-85	w0077		1		85.00	4.30		365.50		
	4th Cross Road Ch:00-25	w0057		1		25.00	4.30		107.50		
	Ch:00-250 1st Main Road	w0106		1		250.00	5.40		1350.00		
	Ch:00-250 MAA BEE Stores	w0114		1		250.00	5.10		1275.00		
	1st Main Road Ch:00-183	w0073		1		183.00	4.00		732.00		
	1st Cross Road Ch:00-190	w0075		1		190.00	4.70		893.00		
	R O Plant Opp Road										
	R O Plant frant area			1		20.00	25.00		500.00		
	Ch:00-57	w0047		1		57.00	4.30		245.10		
	Ch:57-97	w0047		1		40.00	3.20		128.00		
	Ch:97-119	w0047		1		22.00	4.20		92.40		
	Ch:119-149	w0047		1		30.00	4.40		132.00		
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1		40.00	4.10		164.00		
	Ch:40-53	w0092		1		13.00	4.30		55.90		
	Ch:53-116	w0092		1		63.00	3.90		245.70		
	Ch:00-110 2nd Cross Road	w0098		1		110.00	4.30		473.00		
	Chikkasandra Village										
	Sapthgiri College Main Road RHS Roads										
	Ch:0-100 4th Cross Road	w0839		1		100.00	4.50		450.00		
	Ch:0-122 3rd Cross Road	w0847		1		122.00	4.80		585.60		
	Ch:0-125 2nd Cross Road	w0843		1		125.00	5.00		625.00		
	Ch:0-120 5th Cross Road	w0853		1		120.00	5.30		636.00		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1		200.00	5.50		1100.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1		40.00	4.00		160.00		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1		110.00	4.00		440.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1		160.00	4.50		720.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1		220.00	4.50		990.00		
	Ch:0-156 7th Cross Road	w0690		1		156.00	4.50		702.00		
	Ch:0-20 7th Cross Connecting Road			1		20.00	4.00		80.00		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1		115.00	5.00		575.00		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1		105.00	4.00		420.00		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1		100.00	4.00		400.00		
	Ch:100-283	w0883		1		183.00	5.50		1006.50		
	Overly BC										
	Medarahalli Village										
	Pot Hole										

Sl. No	Description of Work	Road ID	Unit	No	Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		12	0.80	1.00		9.60		
	Road Cutting Across the Length									
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		12	5.50	0.80		52.80		
	BWSSB Cutting			2	640.00	0.80		1024.00		
	AGB Layout									
	Across Road Cutting									
	Ch:00-770 60 feet road	w0737		30	9.00	0.30		81.00		
	Ch:00-170 12th Main Road			10	6.00	0.30		18.00		
	Ch:00-400 11th main road	w0660		22	6.50	0.30		42.90		
	Ch:00-260 Family Store Front Road	w0753		25	5.50	0.30		41.25		
	Pot Holes									
	Ch:00-770 60 feet road	w0737		25	0.80	1.00		20.00		
	Ch:00-170 12th Main Road	w0738		12	0.80	1.00		9.60		
	Ch:00-400 11th main road	w0660		21	0.80	1.00		16.80		
	Ch:00-260 Family Store Front Road	w0753		22	0.80	1.00		17.60		
	BWSSB Cutting			2	1600.00	0.80		2560.00		
							Total Qty	**71372.45**	**33.92**	**24,20,953.50**
18	Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading; premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and ialignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 505 of MORTH V revision do - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen KPWD S.R 2018-19 It. No. 21.17.6 Pg.No. 159									
	New BC Road									
	Medarahalli Village									
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-140 Sun Sine School Front Road			1	140.00	6.00	0.05	42.00		
	Ch:00-130 G. Mukesh House Road			1	130.00	4.20	0.05	27.30		
	Ch:00-146 Sri Lakshmi Beside	w0271		1	146.00	4.50	0.05	32.85		
	Ch:00-38 Padma House Front Road			1	38.00	4.80	0.05	9.12		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1	25.00	4.00	0.05	5.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1	25.00	4.00	0.05	5.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1	86.00	5.00	0.05	21.50		
	RHS Road Raj Kaluve to Sri Swamy Bakery									
	Ch:00-105 Raja Kaluve Beside Road	w0265		1	105.00	4.70	0.05	24.68		
	Ch:00-122 Raunak Tower Beside Road	w0269		1	122.00	4.50	0.05	27.45		
	Ch:00-74 Athira House LHS Road			1	74.00	5.00	0.05	18.50		
	Ch:00-75 Athira House RHS Road			1	75.00	5.00	0.05	18.75		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1	115.00	5.00	0.05	28.75		
	railway station track to Dead End									
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		1	620.00	5.60	0.05	173.60		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-35 Mayura Bakery Front Road	w0258		1	35.00	4.00	0.05	7.00		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1	58.00	3.50	0.05	10.15		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-55 Manjushree Bakery Beside	w0267		1	55.00	5.00	0.05	13.75		
	Ch:00-57 Rusoil Bakery Beside	w0255		1	57.00	5.00	0.05	14.25		
	Ch:00-81 3rd Cross Road	w0253		1	81.00	5.00	0.05	20.25		
	Ch:00-73 RR Institution Road	w0251		1	73.00	5.00	0.05	18.25		
	Ch:00-70 Silver Spring International School Road	w0247		1	70.00	5.00	0.05	17.50		
	Ch:00-85 Siddeswara store Beside Road	w0206		1	85.00	4.00	0.05	17.00		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1	35.00	4.00	0.05	7.00		

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:00-100 JMJ Provision Store	w0215		1	100.00	4.50	0.05	22.50		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1	62.00	4.00	0.05	12.40		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1	58.00	4.00	0.05	11.60		
	Ch:00-40 Coss Road			1	40.00	4.00	0.05	8.00		
	Ch:00-55 Sachith House Beside Road	w0210		1	55.00	4.00	0.05	11.00		
	Ch:00-144 Sachith House Front Road	w0204		1	144.00	4.00	0.05	28.80		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1	40.00	4.00	0.05	8.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		1	88.00	4.00	0.05	17.60		
	Ch:00-60 Virabramendra House Front Road	w0200		1	60.00	4.50	0.05	13.50		
	Ch:60-110	w0200		1	50.00	4.80	0.05	12.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		1	185.00	4.00	0.05	37.00		
	Ch:00-155 Kushi backery opp road	w0229		1	155.00	4.00	0.05	31.00		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1	120.00	4.00	0.05	24.00		
	Ch:00-40 Cross Road 1	w0225		1	40.00	4.00	0.05	8.00		
	Ch:00-56 Cross Road 2	w0231		1	56.00	4.00	0.05	11.20		
	Shettihalli Village									
	Ramakrishna Layout									
	Alladamara To Malasandara Road RHS Road									
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1	125.00	4.50	0.05	28.13		
	Ch:00-121 Pavana Nilaya Road	w0961		1	121.00	4.50	0.05	27.23		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1	68.00	4.50	0.05	15.30		
	Byraveshwara nagara									
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1	120.00	4.50	0.05	27.00		
	Ch:00-137 Park Beside Road	w0951		1	137.00	4.50	0.05	30.83		
	Ch:00-192 2nd Cross Road	w0943		1	192.00	4.50	0.05	43.20		
	Ch:00-195 3rd Cross Road	w0941		1	195.00	4.50	0.05	43.88		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1	110.00	4.50	0.05	24.75		
	Ch:00-120 Cross Road	w0935		1	120.00	4.00	0.05	24.00		
	Ch:00-130 Cross Road	w0937		1	130.00	4.00	0.05	26.00		
	A Y R Layout									
	Ch:00-110 Hotel Taste Beside Road			1	110.00	4.50	0.05	24.75		
	Ch:00-85 Saptagiri Nilaya	w0953		1	85.00	4.50	0.05	19.13		
	Ch:00-70 Padma Washing beside	w0813		1	70.00	4.50	0.05	15.75		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1	83.00	4.50	0.05	18.68		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1	85.00	4.50	0.05	19.13		
	Ch:00-90 Gurusai Front Road	w0823		1	90.00	4.50	0.05	20.25		
	Ch:00-95 Cross Road			1	95.00	4.50	0.05	21.38		
	AGB Layout									
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1	565.00	6.00	0.05	169.50		
	Ch:00-100 3rd main Road	w0743		1	100.00	5.50	0.05	27.50		
	Ch:00-148 6th c/s Road	w0620		1	148.00	6.00	0.05	44.40		
	Ch:00-147 6th C Main Road	w0632		1	147.00	5.50	0.05	40.43		
	Ch:00-130 11th Cross Road	w0741		1	130.00	5.50	0.05	35.75		
	Ch:00-127 13th c/s road			1	127.00	6.30	0.05	40.01		
	Ch:127-237 13th c/s Road			1	110.00	5.50	0.05	30.25		
	Ch:00-100 Divya apparel	w0682		1	100.00	5.20	0.05	26.00		
	Ch:00-160 Manasa school Road	w0630	cum	1	160.00	5.50	0.05	44.00		
	Sidedahalli Village Village									
	Sampangiramaiah Layout									
	Ch:00-70 1st c\s road	w0418		1	70.00	4.80	0.05	16.80		
	Ch:00-205 c\s road 2	w0230		1	205.00	5.80	0.05	59.45		
	Ch:00-167 2nd c\s road	w0215		1	167.00	5.20	0.05	43.42		
	Ch:00-140 c\s road 3	w0209		1	140.00	4.80	0.05	33.60		
	Ch:00- 126 c\s road 4	w0115		1	126.00	4.80	0.05	30.24		
	Kirloskar Layout									
	Ch:00-169 New trends	w0109		1	169.00	5.00	0.05	42.25		
	Ch:00-176 9th c\s road	w0101		1	176.00	5.20	0.05	45.76		
	Ch:00-125 3rd c\s road	w0202		1	125.00	6.00	0.05	37.50		
	Ch:00-129 4th c\s road	w0204		1	129.00	5.50	0.05	35.48		
	Ch:00-105 8th c\s road	w0103		1	105.00	5.00	0.05	26.25		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-65 6th c\s road	w0212		1		65.00	5.50	0.05	17.88		
	Ch:00-68 7th c\s road	w0105		1		68.00	5.00	0.05	17.00		
	Ch:00-105 5th c\s road	w0103		1		105.00	5.00	0.05	26.25		
	Ch:00-110 13th c\s road	w0214		1		110.00	5.00	0.05	27.50		
	Ch:00-72 14th c\s road	w0095		1		72.00	5.50	0.05	19.80		
	Ch:00-51 12th c\s road	w0210		1		51.00	4.50	0.05	11.48		
	Ch:00-121 11th c\s road	w0206		1		121.00	4.50	0.05	27.23		
	Ch:00-71 15th c\s road	w0093		1		71.00	4.20	0.05	14.91		
	Ch:00-121 10t c\s road	w0200		1		121.00	5.20	0.05	31.46		
	Ch:00-140 26th c\s road	w0174		1		140.00	5.00	0.05	35.00		
	Ch:00-113 27th c\s road	w0066		1		113.00	5.00	0.05	28.25		
	Ch:00-134 20thc\s road			1		134.00	5.20	0.05	34.84		
	Ch:00-129 25thc\s road	w0176		1		129.00	5.20	0.05	33.54		
	Ch:00-50 24th c\s road	w0180		1		50.00	5.00	0.05	12.50		
	Ch:00-254 22nd c\s road	w0190		1		254.00	5.20	0.05	66.04		
	Ch:00-92 21st c\s road			1		92.00	5.00	0.05	23.00		
	Ch:00-150 28th c\s road	w0194		1		150.00	5.20	0.05	39.00		
	Abbigere Village										
	vijaya lakshmi layout										
	1st Cross Road Ch:00-55	w0051		1		55.00	5.10	0.05	14.03		
	Cross Road Ch:00-55	w0055		1		55.00	5.10	0.05	14.03		
	Cross Road Ch:00-40	w0123		1		40.00	4.90	0.05	9.80		
	Cross Road Ch:00-60	w0051		1		60.00	4.60	0.05	13.80		
	3rd Cross Road Ch:00-85	w0077		1		85.00	4.30	0.05	18.28		
	4th Cross Road Ch:00-25	w0057		1		25.00	4.30	0.05	5.38		
	Ch:00-250 1st Main Road	w0106		1		250.00	5.40	0.05	67.50		
	Ch:00-250 MAA BEE Stores	w0114		1		250.00	5.10	0.05	63.75		
	1st Main Road Ch:00-183	w0073		1		183.00	4.00	0.05	36.60		
	1st Cross Road Ch:00-190	w0075		1		190.00	4.70	0.05	44.65		
	R O Plant Opp Road										
	R O Plant frant area			1		20.00	25.00	0.05	25.00		
	Ch:00-57	w0047		1		57.00	4.30	0.05	12.26		
	Ch:57-97	w0047		1		40.00	3.20	0.05	6.40		
	Ch:97-119	w0047		1		22.00	4.20	0.05	4.62		
	Ch:119-149	w0047		1		30.00	4.40	0.05	6.60		
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1		40.00	4.10	0.05	8.20		
	Ch:40-53	w0092		1		13.00	4.30	0.05	2.80		
	Ch:53-116	w0092		1		63.00	3.90	0.05	12.29		
	Ch:00-110 2nd Cross Road	w0098		1		110.00	4.30	0.05	23.65		
	Chikkasandra Village										
	Sapthgiri College Main Road RHS Roads										
	Ch:0-100 4th Cross Road	w0839		1		100.00	4.50	0.05	22.50		
	Ch:0-122 3rd Cross Road	w0847		1		122.00	4.80	0.05	29.28		
	Ch:0-125 2nd Cross Road	w0843		1		125.00	5.00	0.05	31.25		
	Ch:0-120 5th Cross Road	w0853		1		120.00	5.30	0.05	31.80		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1		200.00	5.50	0.05	55.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1		40.00	4.00	0.05	8.00		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1		110.00	4.00	0.05	22.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1		160.00	4.50	0.05	36.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1		220.00	4.50	0.05	49.50		
	Ch:0-156 7th Cross Road	w0690		1		156.00	4.50	0.05	35.10		
	Ch:0-20 7th Cross Connecting Road			1		20.00	4.00	0.05	4.00		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1		115.00	5.00	0.05	28.75		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1		105.00	4.00	0.05	21.00		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1		100.00	4.00	0.05	20.00		
	Ch:100-283	w0883		1		183.00	5.50	0.05	50.33		
	Overly BC										
	Medarahalli Village										
	Pot Hole										
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		12		0.80	1.00	0.05	0.48		
	Road Cutting Across the Length										
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		12		5.50	0.80	0.05	2.64		

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	BWSSB Cutting			2	640.00	0.80	0.05	51.20		
	AGB Layout									
	Across Road Cutting									
	Ch:00-770 60 feet road	w0737		30	9.00	0.30	0.05	4.05		
	Ch:00-170 12th Main Road			10	6.00	0.30	0.05	0.90		
	Ch:00-400 11th main road	w0660		22	6.50	0.30	0.05	2.15		
	Ch:00-260 Family Store Front Road	w0753		25	5.50	0.30	0.05	2.06		
	Pot Holes									
	Ch:00-770 60 feet road	w0737		25	0.80	1.00	0.05	1.00		
	Ch:00-170 12th Main Road	w0738		12	0.80	1.00	0.05	0.48		
	Ch:00-400 11th main road	w0660		21	0.80	1.00	0.05	0.84		
	Ch:00-260 Family Store Front Road	w0753		22	0.80	1.00	0.05	0.88		
	BWSSB Cutting			2	1600.00	0.80	0.05	128.00		
							Total Qty	**3568.62**	**7292.80**	**2,60,25,231.94**
19	Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications.									
	KPWD S.R 2018-19		It. No.		21.7.		Pg.No.	158		
	New BC Road									
	Medarahalli Village									
	LHS Road Sri Swamy Bakery to Raj Kaluve									
	Ch:00-140 Sun Sine School Front Road			1	140.00	6.00		840.00		
	Ch:00-130 G. Mukesh House Road			1	130.00	4.20		546.00		
	Ch:00-146 Sri Lakshmi Beside	w0271		1	146.00	4.50		657.00		
	Ch:00-38 Padma House Front Road			1	38.00	4.80		182.40		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1	25.00	4.00		100.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1	25.00	4.00		100.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1	86.00	5.00		430.00		
	RHS Road Raj Kaluve to Sri Swamy Bakery									
	Ch:00-105 Raja Kaluve Beside Road	w0265		1	105.00	4.70		493.50		
	Ch:00-122 Raunak Tower Beside Road	w0269		1	122.00	4.50		549.00		
	Ch:00-74 Athira House LHS Road			1	74.00	5.00		370.00		
	Ch:00-75 Athira House RHS Road			1	75.00	5.00		375.00		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1	115.00	5.00		575.00		
	railway station track to Dead End									
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		1	620.00	5.60		3472.00		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-35 Mayura Bakery Front Road	w0258		1	35.00	4.00		140.00		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1	58.00	3.50		203.00		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)									
	Ch:00-55 Manjushree Bakery Beside	w0267		1	55.00	5.00		275.00		
	Ch:00-57 Rusoil Bakery Beside	w0255		1	57.00	5.00		285.00		
	Ch:00-81 3rd Cross Road	w0253		1	81.00	5.00		405.00		
	Ch:00-73 RR Institution Road	w0251		1	73.00	5.00		365.00		
	Ch:00-70 Silver Spring International School Road	w0247		1	70.00	5.00		350.00		
	Ch:00-85 Siddeswara store Beside Road	w0206		1	85.00	4.00		340.00		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1	35.00	4.00		140.00		
	Ch:00-100 JMJ Provision Store	w0215		1	100.00	4.50		450.00		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1	62.00	4.00		248.00		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1	58.00	4.00		232.00		
	Ch:00-40 Coss Road			1	40.00	4.00		160.00		
	Ch:00-55 Sachith House Beside Road	w0210		1	55.00	4.00		220.00		
	Ch:00-144 Sachith House Front Road	w0204		1	144.00	4.00		576.00		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1	40.00	4.00		160.00		
	Ch:00-88 Raj Sai Villa Beside	w0202		1	88.00	4.00		352.00		
	Ch:00-60 Virabramendra House Front Road	w0200		1	60.00	4.50		270.00		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:60-110	w0200		1		50.00	4.80		240.00		
	Ch:00-185 Nanjunda swami Front Road	w0215		1		185.00	4.00		740.00		
	Ch:00-155 Kushi backery opp road	w0229		1		155.00	4.00		620.00		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1		120.00	4.00		480.00		
	Ch:00-40 Cross Road 1	w0225		1		40.00	4.00		160.00		
	Ch:00-56 Cross Road 2	w0231		1		56.00	4.00		224.00		
	Shettihalli Village										
	Ramakrishna Layout										
	Alladamara To Malasandara Road RHS Road										
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1		125.00	4.50		562.50		
	Ch:00-121 Pavana Nilaya Road	w0961		1		121.00	4.50		544.50		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1		68.00	4.50		306.00		
	Byraveshwara nagara										
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1		120.00	4.50		540.00		
	Ch:00-137 Park Beside Road	w0951		1		137.00	4.50		616.50		
	Ch:00-192 2nd Cross Road	w0943		1		192.00	4.50		864.00		
	Ch:00-195 3rd Cross Road	w0941		1		195.00	4.50		877.50		
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1		110.00	4.50		495.00		
	Ch:00-120 Cross Road	w0935		1		120.00	4.00		480.00		
	Ch:00-130 Cross Road	w0937		1		130.00	4.00		520.00		
	A Y R Layout										
	Ch:00-110 Hotel Taste Beside Road			1		110.00	4.50		495.00		
	Ch:00-85 Saptagiri Nilaya	w0953		1		85.00	4.50		382.50		
	Ch:00-70 Padma Washing beside	w0813		1		70.00	4.50		315.00		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1		83.00	4.50		373.50		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1		85.00	4.50		382.50		
	Ch:00-90 Gurusai Front Road	w0823		1		90.00	4.50		405.00		
	Ch:00-95 Cross Road			1		95.00	4.50		427.50		
	AGB Layout										
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1		565.00	6.00		3390.00		
	Ch:00-100 3rd main Road	w0743		1		100.00	5.50		550.00		
	Ch:00-148 6th c/s Road	w0620	Sqm	1		148.00	6.00		888.00		
	Ch:00-147 6th C Main Road	w0632		1		147.00	5.50		808.50		
	Ch:00-130 11th Cross Road	w0741		1		130.00	5.50		715.00		
	Ch:00-127 13th c/s road			1		127.00	6.30		800.10		
	Ch:127-237 13th c/s Road			1		110.00	5.50		605.00		
	Ch:00-100 Divya apparel	w0682		1		100.00	5.20		520.00		
	Ch:00-160 Manasa school Road	w0630		1		160.00	5.50		880.00		
	Sidedahalli Village Village										
	Sampangiramaiah Layout										
	Ch:00-70 1st c\s road	w0418		1		70.00	4.80		336.00		
	Ch:00-205 c\s road 2	w0230		1		205.00	5.80		1189.00		
	Ch:00-167 2nd c\s road	w0215		1		167.00	5.20		868.40		
	Ch:00-140 c\s road 3	w0209		1		140.00	4.80		672.00		
	Ch:00- 126 c\s road 4	w0115		1		126.00	4.80		604.80		
	Kirloskar Layout										
	Ch:00-169 New trends	w0109		1		169.00	5.00		845.00		
	Ch:00-176 9th c\s road	w0101		1		176.00	5.20		915.20		
	Ch:00-125 3rd c\s road	w0202		1		125.00	6.00		750.00		
	Ch:00-129 4th c\s road	w0204		1		129.00	5.50		709.50		
	Ch:00-105 8th c\s road	w0103		1		105.00	5.00		525.00		
	Ch:00-65 6th c\s road	w0212		1		65.00	5.50		357.50		
	Ch:00-68 7th c\s road	w0105		1		68.00	5.00		340.00		
	Ch:00-105 5th c\s road	w0103		1		105.00	5.00		525.00		
	Ch:00-110 13th c\s road	w0214		1		110.00	5.00		550.00		
	Ch:00-72 14th c\s road	w0095		1		72.00	5.50		396.00		
	Ch:00-51 12th c\s road	w0210		1		51.00	4.50		229.50		
	Ch:00-121 11th c\s road	w0206		1		121.00	4.50		544.50		
	Ch:00-71 15th c\s road	w0093		1		71.00	4.20		298.20		
	Ch:00-121 10t c\s road	w0200		1		121.00	5.20		629.20		
	Ch:00-140 26th c\s road	w0174		1		140.00	5.00		700.00		
	Ch:00-113 27th c\s road	w0066		1		113.00	5.00		565.00		
	Ch:00-134 20thc\s road			1		134.00	5.20		696.80		
	Ch:00-129 25thc\s road	w0176		1		129.00	5.20		670.80		

Sl. No	Description of Work	Road ID	Unit	No	Dimension			Quantity	Rate	Amount
					L	B	D		in Rs.	in Rs.
	Ch:00-50 24th c\s road	w0180		1	50.00	5.00		250.00		
	Ch:00-254 22nd c\s road	w0190		1	254.00	5.20		1320.80		
	Ch:00-92 21st c\s road			1	92.00	5.00		460.00		
	Ch:00-150 28th c\s road	w0194		1	150.00	5.20		780.00		
	Abbigere Village									
	vijaya lakshmi layout									
	1st Cross Road Ch:00-55	w0051		1	55.00	5.10		280.50		
	Cross Road Ch:00-55	w0055		1	55.00	5.10		280.50		
	Cross Road Ch:00-40	w0123		1	40.00	4.90		196.00		
	Cross Road Ch:00-60	w0051		1	60.00	4.60		276.00		
	3rd Cross Road Ch:00-85	w0077		1	85.00	4.30		365.50		
	4th Cross Road Ch:00-25	w0057		1	25.00	4.30		107.50		
	Ch:00-250 1st Main Road	w0106		1	250.00	5.40		1350.00		
	Ch:00-250 MAA BEE Stores	w0114		1	250.00	5.10		1275.00		
	1st Main Road Ch:00-183	w0073		1	183.00	4.00		732.00		
	1st Cross Road Ch:00-190	w0075		1	190.00	4.70		893.00		
	R O Plant Opp Road									
	R O Plant frant area			1	20.00	25.00		500.00		
	Ch:00-57	w0047		1	57.00	4.30		245.10		
	Ch:57-97	w0047		1	40.00	3.20		128.00		
	Ch:97-119	w0047		1	22.00	4.20		92.40		
	Ch:119-149	w0047		1	30.00	4.40		132.00		
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1	40.00	4.10		164.00		
	Ch:40-53	w0092		1	13.00	4.30		55.90		
	Ch:53-116	w0092		1	63.00	3.90		245.70		
	Ch:00-110 2nd Cross Road	w0098		1	110.00	4.30		473.00		
	Chikkasandra Village									
	Sapthgiri College Main Road RHS Roads									
	Ch:0-100 4th Cross Road	w0839		1	100.00	4.50		450.00		
	Ch:0-122 3rd Cross Road	w0847		1	122.00	4.80		585.60		
	Ch:0-125 2nd Cross Road	w0843		1	125.00	5.00		625.00		
	Ch:0-120 5th Cross Road	w0853		1	120.00	5.30		636.00		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1	200.00	5.50		1100.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1	40.00	4.00		160.00		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1	110.00	4.00		440.00		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1	160.00	4.50		720.00		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1	220.00	4.50		990.00		
	Ch:0-156 7th Cross Road	w0690		1	156.00	4.50		702.00		
	Ch:0-20 7th Cross Connecting Road			1	20.00	4.00		80.00		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1	115.00	5.00		575.00		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1	105.00	4.00		420.00		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1	100.00	4.00		400.00		
	Ch:100-283	w0883		1	183.00	5.50		1006.50		
	Overly BC									
	Medarahalli Village									
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		1	510.00	6.00		3060.00		
	AGB Layout									
	Ch:00-770 60 feet road	w0737		1	770.00	9.00		6930.00		
	Ch:00-170 12th Main Road	w0738		1	170.00	6.00		1020.00		
	Ch:00-400 11th main road	w0660		1	400.00	6.50		2600.00		
	Ch:00-260 Family Store Front Road	w0753		1	260.00	5.50		1430.00		
							Total Qty	**82518.90**	**12.72**	**10,49,640.41**
20	Providing and laying bituminous concrete 40mm thick with hot mix plant,do - using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4% VG-30 Bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015.										
	KPWD S.R 2018-19		It. No.		21.22.6		Pg.No.	162		
	New BC Road									
	Medarahalli Village									

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	LHS Road Sri Swamy Bakery to Raj Kaluve										
	Ch:00-140 Sun Sine School Front Road			1		140.00	6.00	0.03	25.20		
	Ch:00-130 G. Mukesh House Road			1		130.00	4.20	0.03	16.38		
	Ch:00-146 Sri Lakshmi Beside	w0271		1		146.00	4.50	0.03	19.71		
	Ch:00-38 Padma House Front Road			1		38.00	4.80	0.03	5.47		
	Ch:00-25 Sri Sai Nivasa Front Road	w0267		1		25.00	4.00	0.03	3.00		
	Ch:00-25 Sri Maruthi Nilaya	w0260		1		25.00	4.00	0.03	3.00		
	Ch:25-111 Sri Maruthi Nilaya	w0261		1		86.00	5.00	0.03	12.90		
	RHS Road Raj Kaluve to Sri Swamy Bakery										
	Ch:00-105 Raja Kaluve Beside Road	w0265		1		105.00	4.70	0.03	14.81		
	Ch:00-122 Raunak Tower Beside Road	w0269		1		122.00	4.50	0.03	16.47		
	Ch:00-74 Athira House LHS Road			1		74.00	5.00	0.03	11.10		
	Ch:00-75 Athira House RHS Road			1		75.00	5.00	0.03	11.25		
	Ch:00-115 Sri Chandappa Nilaya Beside Road			1		115.00	5.00	0.03	17.25		
	railway station track to Dead End										
	Ch:510-1130 Main Road Sunshine Public School to Dead End	w0256		1		620.00	5.60	0.04	138.88		
	LHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-35 Mayura Bakery Front Road	w0258		1		35.00	4.00	0.03	4.20		
	Ch:00-58 Santhosh Nilaya Front Road	w0258		1		58.00	3.50	0.03	6.09		
	RHS Road Raja Kaluve to Allada mara (RR Institute Road)										
	Ch:00-55 Manjushree Bakery Beside	w0267		1		55.00	5.00	0.03	8.25		
	Ch:00-57 Rusoil Bakery Beside	w0255		1		57.00	5.00	0.03	8.55		
	Ch:00-81 3rd Cross Road	w0253		1		81.00	5.00	0.03	12.15		
	Ch:00-73 RR Institution Road	w0251		1		73.00	5.00	0.03	10.95		
	Ch:00-70 Silver Spring International School Road	w0247		1		70.00	5.00	0.03	10.50		
	Ch:00-85 Siddeswara store Beside Road	w0206		1		85.00	4.00	0.03	10.20		
	Ch:00-35 Kendaganeshwara swami House Front Road	w0219		1		35.00	4.00	0.03	4.20		
	Ch:00-100 JMJ Provision Store	w0215		1		100.00	4.50	0.03	13.50		
	Ch:00-62 Ameen Maneil House Front Road	w0217		1		62.00	4.00	0.03	7.44		
	Ch:00-58 Spoorthi Enterprises Beside	w0227		1		58.00	4.00	0.03	6.96		
	Ch:00-40 Coss Road			1		40.00	4.00	0.03	4.80		
	Ch:00-55 Sachith House Beside Road	w0210		1		55.00	4.00	0.03	6.60		
	Ch:00-144 Sachith House Front Road	w0204		1		144.00	4.00	0.03	17.28		
	Ch:00-40 Jyothi Sankar House Beside Road	w0202		1		40.00	4.00	0.03	4.80		
	Ch:00-88 Raj Sai Villa Beside	w0202		1		88.00	4.00	0.03	10.56		
	Ch:00-60 Virabramendra House Front Road	w0200		1		60.00	4.50	0.03	8.10		
	Ch:60-110	w0200		1		50.00	4.80	0.03	7.20		
	Ch:00-185 Nanjunda swami Front Road	w0215		1		185.00	4.00	0.03	22.20		
	Ch:00-155 Kushi backery opp road	w0229		1		155.00	4.00	0.03	18.60		
	Ch:00-120 Sri Vinayaka House Beside Road	w0223		1		120.00	4.00	0.03	14.40		
	Ch:00-40 Cross Road 1	w0225		1		40.00	4.00	0.03	4.80		
	Ch:00-56 Cross Road 2	w0231		1		56.00	4.00	0.03	6.72		
	Shettihalli Village										
	Ramakrishna Layout										
	Alladamara To Malasandara Road RHS Road										
	Ch:00-125 Sri Ganesha Trades Beside	w0967		1		125.00	4.50	0.03	16.88		
	Ch:00-121 Pavana Nilaya Road	w0961		1		121.00	4.50	0.03	16.34		
	Ch:00-68 Pavana Nilaya Front Road	w0800		1		68.00	4.50	0.03	9.18		
	Byraveshwara nagara										
	Ch:00-120 Kartikeya House Road (L Shape)	w0955		1		120.00	4.50	0.03	16.20		
	Ch:00-137 Park Beside Road	w0951		1		137.00	4.50	0.03	18.50		
	Ch:00-192 2nd Cross Road	w0943		1		192.00	4.50	0.03	25.92		
	Ch:00-195 3rd Cross Road	w0941		1		195.00	4.50	0.03	26.33		

Sl. No	Description of Work	Road ID	Unit	No		Dimension			Quantity	Rate	Amount
						L	B	D		in Rs.	in Rs.
	Ch:00-110 4th Cross Road (Bavanankitha House Front Road) L shape	w0933		1		110.00	4.50	0.03	14.85		
	Ch:00-120 Cross Road	w0935		1		120.00	4.00	0.03	14.40		
	Ch:00-130 Cross Road	w0937		1		130.00	4.00	0.03	15.60		
	A Y R Layout										
	Ch:00-110 Hotel Taste Beside Road			1		110.00	4.50	0.03	14.85		
	Ch:00-85 Saptagiri Nilaya	w0953		1		85.00	4.50	0.03	11.48		
	Ch:00-70 Padma Washing beside	w0813		1		70.00	4.50	0.03	9.45		
	Ch:00-83 Mukambika Stores Beside Road	w0827		1		83.00	4.50	0.03	11.21		
	Ch:00-85 Kantamma Nilaya Front Road	w0825		1		85.00	4.50	0.03	11.48		
	Ch:00-90 Gurusai Front Road	w0823		1		90.00	4.50	0.03	12.15		
	Ch:00-95 Cross Road			1		95.00	4.50	0.03	12.83		
	AGB Layout										
	Ch:00-565 6th Main Road (Thoom kuzy Hose Front)	w0743		1		565.00	6.00	0.04	135.60		
	Ch:00-100 3rd main Road	w0743		1		100.00	5.50	0.04	22.00		
	Ch:00-148 6th c/s Road	w0620		1		148.00	6.00	0.04	35.52		
	Ch:00-147 6th C Main Road	w0632		1		147.00	5.50	0.04	32.34		
	Ch:00-130 11th Cross Road	w0741	Cum	1		130.00	5.50	0.04	28.60		
	Ch:00-127 13th c/s road			1		127.00	6.30	0.04	32.00		
	Ch:127-237 13th c/s Road			1		110.00	5.50	0.04	24.20		
	Ch:00-100 Divya apparel	w0682		1		100.00	5.20	0.04	20.80		
	Ch:00-160 Manasa school Road	w0630		1		160.00	5.50	0.04	35.20		
	Sidedahalli Village Village										
	Sampangiramaiah Layout										
	Ch:00-70 1st c\s road	w0418		1		70.00	4.80	0.03	10.08		
	Ch:00-205 c\s road 2	w0230		1		205.00	5.80	0.03	35.67		
	Ch:00-167 2nd c\s road	w0215		1		167.00	5.20	0.03	26.05		
	Ch:00-140 c\s road 3	w0209		1		140.00	4.80	0.03	20.16		
	Ch:00- 126 c\s road 4	w0115		1		126.00	4.80	0.03	18.14		
	Kirloskar Layout										
	Ch:00-169 New trends	w0109		1		169.00	5.00	0.03	25.35		
	Ch:00-176 9th c\s road	w0101		1		176.00	5.20	0.03	27.46		
	Ch:00-125 3rd c\s road	w0202		1		125.00	6.00	0.03	22.50		
	Ch:00-129 4th c\s road	w0204		1		129.00	5.50	0.03	21.29		
	Ch:00-105 8th c\s road	w0103		1		105.00	5.00	0.03	15.75		
	Ch:00-65 6th c\s road	w0212		1		65.00	5.50	0.03	10.73		
	Ch:00-68 7th c\s road	w0105		1		68.00	5.00	0.03	10.20		
	Ch:00-105 5th c\s road	w0103		1		105.00	5.00	0.03	15.75		
	Ch:00-110 13th c\s road	w0214		1		110.00	5.00	0.03	16.50		
	Ch:00-72 14th c\s road	w0095		1		72.00	5.50	0.03	11.88		
	Ch:00-51 12th c\s road	w0210		1		51.00	4.50	0.03	6.89		
	Ch:00-121 11th c\s road	w0206		1		121.00	4.50	0.03	16.34		
	Ch:00-71 15th c\s road	w0093		1		71.00	4.20	0.03	8.95		
	Ch:00-121 10t c\s road	w0200		1		121.00	5.20	0.03	18.88		
	Ch:00-140 26th c\s road	w0174		1		140.00	5.00	0.03	21.00		
	Ch:00-113 27th c\s road	w0066		1		113.00	5.00	0.03	16.95		
	Ch:00-134 20thc\s road			1		134.00	5.20	0.03	20.90		
	Ch:00-129 25thc\s road	w0176		1		129.00	5.20	0.03	20.12		
	Ch:00-50 24th c\s road	w0180		1		50.00	5.00	0.03	7.50		
	Ch:00-254 22nd c\s road	w0190		1		254.00	5.20	0.03	39.62		
	Ch:00-92 21st c\s road			1		92.00	5.00	0.03	13.80		
	Ch:00-150 28th c\s road	w0194		1		150.00	5.20	0.03	23.40		
	Abbigere Village										
	vijaya lakshmi layout										
	1st Cross Road Ch:00-55	w0051		1		55.00	5.10	0.03	8.42		
	Cross Road Ch:00-55	w0055		1		55.00	5.10	0.03	8.42		
	Cross Road Ch:00-40	w0123		1		40.00	4.90	0.03	5.88		
	Cross Road Ch:00-60	w0051		1		60.00	4.60	0.03	8.28		
	3rd Cross Road Ch:00-85	w0077		1		85.00	4.30	0.03	10.97		
	4th Cross Road Ch:00-25	w0057		1		25.00	4.30	0.03	3.23		
	Ch:00-250 1st Main Road	w0106		1		250.00	5.40	0.03	40.50		
	Ch:00-250 MAA BEE Stores	w0114		1		250.00	5.10	0.03	38.25		
	1st Main Road Ch:00-183	w0073		1		183.00	4.00	0.03	21.96		
	1st Cross Road Ch:00-190	w0075		1		190.00	4.70	0.03	26.79		
	R O Plant Opp Road										
	R O Plant frant area			1		20.00	25.00	0.03	15.00		
	Ch:00-57	w0047		1		57.00	4.30	0.03	7.35		
	Ch:57-97	w0047		1		40.00	3.20	0.03	3.84		
	Ch:97-119	w0047		1		22.00	4.20	0.03	2.77		
	Ch:119-149	w0047		1		30.00	4.40	0.03	3.96		

Sl. No	Description of Work	Road ID	Unit	No		Dimension L	Dimension B	Dimension D	Quantity	Rate in Rs.	Amount in Rs.
	Ch:00-40 Sri Munjanth Swami Nilaya 1st Cross Road	w0092		1		40.00	4.10	0.03	4.92		
	Ch:40-53	w0092		1		13.00	4.30	0.03	1.68		
	Ch:53-116	w0092		1		63.00	3.90	0.03	7.37		
	Ch:00-110 2nd Cross Road	w0098		1		110.00	4.30	0.03	14.19		
	Chikkasandra Village										
	Sapthgiri College Main Road RHS Roads										
	Ch:0-100 4th Cross Road	w0839		1		100.00	4.50	0.03	13.50		
	Ch:0-122 3rd Cross Road	w0847		1		122.00	4.80	0.03	17.57		
	Ch:0-125 2nd Cross Road	w0843		1		125.00	5.00	0.03	18.75		
	Ch:0-120 5th Cross Road	w0853		1		120.00	5.30	0.03	19.08		
	Ch:0-200 1st Main Road(Hemadriya Front)	w0714		1		200.00	5.50	0.03	33.00		
	Ch:0-40 Cross Road(Krishna House Road)	w0855		1		40.00	4.00	0.03	4.80		
	Ch:0-110 7th Cross Road(chicken World Front)	w0857		1		110.00	4.00	0.03	13.20		
	Ch:0-160 Dilip Icecrim Point Front Road	w0869		1		160.00	4.50	0.03	21.60		
	Ch:00-220 10th Cross Road (555 Star P.G opp Road)	w0871		1		220.00	4.50	0.03	29.70		
	Ch:0-156 7th Cross Road	w0690		1		156.00	4.50	0.03	21.06		
	Ch:0-20 7th Cross Connecting Road			1		20.00	4.00	0.03	2.40		
	Ch:00-115 3rd Cross Road(Janaki Bajar Shop Opp)			1		115.00	5.00	0.03	17.25		
	Ch:0-105 Sri Renukadevi Condiments Opp Road			1		105.00	4.00	0.03	12.60		
	Ch:0-100 Sri Bairalingappa Road (Sri Rammandira Beside Road)	w0883		1		100.00	4.00	0.03	12.00		
	Ch:100-283	w0883		1		183.00	5.50	0.03	30.20		
	Overly BC										
	Medarahalli Village										
	Medarahalli Village										
	Ch:00-510 Main Road Railway station track to Sunshine Public School	w0256		1		510.00	6.00	0.04	122.40		
	AGB Layout										
	Ch:00-770 60 feet road	w0737		1		770.00	9.00	0.04	277.20		
	Ch:00-170 12th Main Road	w0739		1		170.00	6.00	0.04	40.80		
	Ch:00-400 11th main road	w0660		1		400.00	6.50	0.04	104.00		
	Ch:00-260 Family Store Front Road	w0753		1		260.00	5.50	0.04	57.20		
								Total Qty	**2752.25**	**8450.32**	**2,32,57,393.22**
21	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803										
	KPWD S.R 2018-19		It. No.		24.15		Pg.No.	182			
	Edge Lane			2	1	15858.00	0.10		3171.60		
	Center line		Cum	1	1	5286.00	0.10		528.60		
								Total Qty	**3700.20**	**454.74**	**16,82,628.95**

Sl. No	Description of Work	Road ID	Unit	No	Dimension L	B	D	Quantity	Rate in Rs.	Amount in Rs.
22	Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/ NH/33023/10-97 – DO III Dt 11.06. 1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 mm and height not less than 30 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer.(P.No-187,I No-24.41)									
	KPWD S.R 2018-19		It. No.		24.41		Pg.No.	187		
	Per 6m Interval		No	2	1	317.50			635.00		
								Total Qty	635.00	357.22	2,26,834.70
										Total Constrution cost	1575,84,339.26
										GST 12%	189,10,120.71
										Design Report,Proof Checking & PMC Amount	34,66,855.46
										Sub Total	1799,61,315.43
										Miscellaneous & Rounding Off	38,684.57
										Grand Total	1800,00,000.00

Certificate:-

1. The workspot was inspected and work is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike Limits.
3. The rates adopted based on the PWD SR Bangalore Circle for year 2018-19
4. The provisions made in the estimate are necessary and essential.

SAI CONSULTANTS

Consultant
For Sri Sai Consultants

Assistant Engineer
Ward 12,14
BBMP - Bangalore

Assistant Executive Engineer
Shettyhalli ,Dasarahalli Sub-Division
BBMP Bangalore

Executive Engineer
Dasarahalli
BBMP - Bangalore

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರ
ಶೆಟ್ಟಿಹಳ್ಳಿ ಉಪವಿಭಾಗ. ದಾಸರಹಳ್ಳಿ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಎಸ್.ಎಂ. ರಸ್ತೆ, ರವೀಂದ್ರನಗರ, ಬೆಂಗಳೂರು.

ADMINISTRATIVELY SANCTIONED FOR Rs.
(Rupees One hundredeight hundred
lakhs only
Under the Head of Account P.3867 SFC
Restoration of villages Roads
Drainage by BWSSB for WS works
Registered as no EE(D.D.)/AS...05.....Subject
to conditions contained in Enclosed Memo
No BBMP/CE/DD/05/2022-23 Dt: 17.10.2022

Exe. Eng
JE/AE. (DASARAHALLI) BBMP

Technically Sanctione for Rs. 180.00 Lakhs/-
Rs. In words Rs: One Hundred &
Eighty lakhs only/-
Under
Job Code No.
Registered as CE No CE/D2/TS/28/2021-22 Subject
to conditions contained in Enclosed Memo
No CE/D2/TS/28/2021-22 Dt: 05/10/2021

AE/JE. TA CE(D)